

NOTICE TO CONTRACTORS

CALL ORDER 400  
 STATE PROJECT NO. MISC-136-5(1015)  
 LOCATION: US-136, RUSKIN EAST & WEST CULVERTS  
 COUNTIES: NUCKOLLS

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on April 14, 2011. At that time the bids will be opened and read for GRAD CULV SEED

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: GRADING CULVERTS

Length: 12.9 MILES  
 START DATE 06/27/2011 WORKING DAYS 90  
 Price Range \$ 500,000 to \$ 2,000,000

Plans and specifications may be seen beginning March 22, 2011 at the Lincoln Central Office and March 28, 2011 at the District Engineer's Office at GRAND ISLAND

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL		EACH	\$ 5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	125	SHEETS	\$ 31.25
CROSS SECTIONS (SHEETS X1 THRU X116)	116	SHEETS	\$ 29.00
STANDARD PLANS	16	SHEETS	\$ 4.00

SHEET NO.

1	TITLE PAGE
2	INDEX OF SHEETS
2-T	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-W1 - 2-W23	WETLANDS
2-H1 - 2-H4	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
2-L1 - 2-L12	EROSION CONTROL
3 - 14	PLAN SHEETS
15 - 22	EARTHWORK DATA SHEETS
23 - 37	DRAINAGE STRUCTURE CROSS SECTIONS
38 - 40	SPECIAL PLAN 1C 4' X 4' SINGLE SPAN RC BOX CULVERT STA. 33+63 LT
41 - 42	SPECIAL PLAN 2C 5' X 4' SINGLE SPAN RC BOX CULVERT STA. 64+67
43 - 44	SPECIAL PLAN 3C 10' X 8' TWIN SPAN RC BOX CULVERT STA. 276+54
45 - 46	SPECIAL PLAN 4C 6' X 4' SINGLE SPAN RC BOX CULVERT STA. 325+49
47 - 48	SPECIAL PLAN 5C 6' X 6' SINGLE SPAN RC BOX CULVERT STA. 407+72
49 - 50	SPECIAL PLAN 6C 4' X 3' SINGLE SPAN RC BOX CULVERT STA. 551+18.00
51 - 53	SPECIAL PLAN 7C 10' X 4' SINGLE SPAN RC BOX CULVERT STA. 557+79.00 LT
54 - 55	SPECIAL PLAN 8C 8' X 4' SINGLE SPAN RC BOX CULVERT STA. 568+47
56 - 58	SPECIAL PLAN 9C 8' X 6' SINGLE SPAN RC BOX CULVERT STA. 583+04.00 LT
59 - 60	SPECIAL PLAN 10C TEMPORARY SILT CHECKS

R1 - R23            RIGHT-OF-WAY SHEETS  
X1 - X116           CROSS SECTIONS

STANDARD PLANS

403-R2        (2 SHEETS) BENDS AND BREAKS FOR CONCRETE  
                  BOX CULVERTS  
410-R3        (2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES  
425-R4        COLLARS AND ELBOWS FOR CONCRETE PIPES  
501-R5        (3 SHEETS) EROSION CONTROL  
502            SILT FENCE DETAILS  
804            PRECAST CONCRETE R.O.W. MARKER  
920-R5        (2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE  
921-R5        (2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE  
922-R8        (2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and  
should not be used for bidding purposes. The Department  
reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL		5 EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		947 MGAL
RIGHT-OF-WAY MARKERS		220 EACH
EARTHWORK MEASURED IN EMBANKMENT		67,625 CY
REMOVE BUILDING		1 EACH
AT STA. 199+00 TO STA. 199+30 RT.		
COVER CROP SEEDING		48 ACRE
EROSION CONTROL, CLASS 1D		33,251 SY
FABRIC SILT FENCE-LOW POROSITY		15,016 LF

GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
RIPRAP FILTER FABRIC		639 SY
REMOVE HEADWALLS FROM CULV		61 EACH
PREPARATION OF STRUCTURE		1 EACH
AT STA. 33+63		
PREPARATION OF STRUCTURE		1 EACH
AT STA. 64+67		
PREPARATION OF STRUCTURE		1 EACH
AT STA. 325+49		
PREPARATION OF STRUCTURE		1 EACH
AT STA. 407+72		
PREPARATION OF STRUCTURE		1 EACH
AT STA. 551+18		
PREPARATION OF STRUCTURE		1 EACH
AT STA. 557+79		
PREPARATION OF STRUCTURE		1 EACH
AT STA. 568+47		
PREPARATION OF STRUCTURE		1 EACH
AT STA. 583+04		
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL		385 CY
EXCAVATION FOR BOX CULVERTS		268 CY
47B-3000 CONC FOR BOX CULV		310 CY
47B-3000 CONC FOR CONCRETE CO		2 CY
RE-STEEL FOR BOX CULVERT		26,916 LB
RE-STEEL FOR COLLARS		140 LB
42" FLARED-END SECTION		1 EACH
54" FLARED-END SECTION		1 EACH
24" METAL FLARED-END SECTION		24 EACH
30" METAL FLARED-END SECTION		11 EACH
36" METAL FLARED-END SECTION		7 EACH
48" METAL FLARED-END SECTION		4 EACH

24" CONCRETE FLARED-END SECTION	4 EACH
30" CONCRETE FLARED-END SECTION	2 EACH
42" CONCRETE FLARED-END SECTION	9 EACH
54" CONCRETE FLARED-END SECTION	3 EACH
60" CONCRETE FLARED-END SECTION	2 EACH
CULVERT SANDFILL	97 CY
JACKING 24" CULV PIPE, 2 CLASS IV	90 LF
JACK 30" CULV PIPE 2 CLASS IV	50 LF
JACKING 42" CULV PIPE, 2 CLASS IV	279 LF
JACKING 54" CULV PIPE, 2 CLASS IV	123 LF
JACKING 60" CULV PIPE, 2 CLASS IV	52 LF
ROCK RIPRAP, TYPE A	152 TON
ROCK RIPRAP, TYPE B	299 TON
24" CULV PIPE 2 CLASS IV	90 LF
30" CULV PIPE 2 CLASS IV	50 LF
42" CULV PIPE 2 CLASS IV	279 LF
54" CULV PIPE 2 CLASS IV	123 LF
60" CULV PIPE, 2 CLASS IV	52 LF
42" CULV PIPE 2,5	10 LF
54" CULV PIPE 2,5	10 LF
24" CULV PIPE 3,4,5	273 LF
30" CULV PIPE 3,4,5	265 LF
36" CULV PIPE 3,4,5	102 LF
48" CULV PIPE 3,4,5	132 LF
24" CULV PIPE 3,4,5,6	127 LF

GROUP 4A CULVERTS

MOBILIZATION	LUMP	LUMP
PREPARATION OF STRUCTURE AT STA. 276+54		1 EACH
EXCAVATION FOR BOX CULVERTS		52 CY
47B-3000 CONC FOR BOX CULV		87 CY
RE-STEEL FOR BOX CULVERT		8,306 LB

GROUP 5 SEEDING

MOBILIZATION	LUMP	LUMP
SEEDING, TYPE A		10 ACRE
SEEDING, TYPE B		38 ACRE
MULCH		108 TON

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II		1,500 BDAY
BARRICADE, TYPE III		8,620 BDAY
TEMPORARY SIGN DAY		120 EACH
SIGN DAY		10,670 EACH
FLAGGING		30 DAY
FURNISHING AND OPERATING PILOT VEHICLE		15 DAY
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED		160 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED		160 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED		160 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.		160 HOUR
TEMPORARY SILT CHECK		1,000 LF
TEMPORARY SILT FENCE		1,000 LF
TEMPORARY MULCH		4 TON