

NOTICE TO CONTRACTORS

CALL ORDER 415  
 STATE PROJECT NO. RD-4-5(1004)  
 LOCATION: N-4 & S85D, N. JCT. US-81 EAST  
 COUNTIES: THAYER

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on April 14, 2011. At that time the bids will be opened and read for BR GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 10.9 MILES  
 START DATE 06/13/2011 WORKING DAYS 85  
 Price Range \$ 1,000,000 to \$ 3,000,000

Plans and specifications may be seen beginning March 22, 2011 at the Lincoln Central Office and March 28, 2011 at the District Engineer's Office at GRAND ISLAND  
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	54	SHEETS	\$	13.50
CROSS SECTIONS (SHEETS X1 THRU X4)	4	SHEETS	\$	1.00
STANDARD PLANS	14	SHEETS	\$	3.50

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T5	TYPICAL CROSS SECTIONS
2-S1 - 2-S3	SUMMARY OF QUANTITIES
2-A1 - 2-A11	PHOTO MAPS
2-H1 - 2-H3	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
3 - 13	PLAN SHEETS
14	TEMPORARY PAVEMENT MARKING PLAN
15	TYPICAL TRAFFIC CONTROL PLAN--TYPICAL YIELD CONTROL FOR LOW VOLUME, ONE LANE, TWO WAY TRAFFIC (BARRELS ONLY)
16	EARTHWORK DATA SHEET
17 - 18	SPECIAL PLAN 1C CONCRETE SLAB BRIDGE--GENERAL BRIDGE REPAIR STA. 377+96.00
19 - 20	SPECIAL PLAN 2C TWIN TEE PRESTRESSED GIRDER BRIDGE--REPAIR STA. 562+67.00
21 - 23	SPECIAL PLAN 3C SLAB BRIDGE--REHAB STA. 1040+03.00
24 - 32	SPECIAL PLAN 4C GUARDRAIL PLAN
X1 - X4	CROSS SECTIONS

STANDARD PLANS

108-R4	SUPERELEVATION PLAN FOR CONCRETE AND BITUMINOUS SURFACING
307-R1	MAILBOX TURNOUT
309	MAILBOX SUPPORT POST
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
901-R9	HIGHWAY DELINEATORS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 6 BRIDGE AT STA. 377+96.00

MOBILIZATION	LUMP	LUMP
ABUTMENT REPAIR		10 SF
CONCRETE REPAIR		250 SF

GROUP 6A BRIDGE AT STA. 562+67.00

MOBILIZATION	LUMP	LUMP
FLOWABLE FILL CONCRETE		1 CY
CLASS II REPAIR		12 SY
GIRDER REPAIR		4 EACH
SEALING DECK CRACKS		25 LF

GROUP 6B BRIDGE AT STA. 1040+03.00

MOBILIZATION	LUMP	LUMP
47BD-4000 CONC FOR BRIDGE		3 CY
PREP BRIDGE		1 EACH
AT STA. 1040+03.00		
EPOXY COATED RE-STEEL		520 LB
CONCRETE REPAIR		198 SF
CURB REPAIR		20 SF

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
W-BEAM GUARDRAIL		212 LF
REMOVE GUARDRAIL		1,062 LF
BRIDGE APPROACH SECTIONS		12 EACH
GUARDRAIL END TREATMENT, TYPE II		12 EACH

GROUP 9 BITUMINOUS

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
INSTALL CHEVRONS		10 EACH
EARTHWORK MEASURED IN EMBANKMENT		737 CY
GRAVEL SURFACE COURSE		100 CY
CRUSHED ROCK SURFACE COURSE		75 CY
SPEC SURF CRSE FOR MAILBOX TURNOUTS		703 SY
MAILBOX POST		7 EACH
CONC PVMT REPAIR TYPE A FULL DEPTH		10 CY
CONC PVMT REPAIR TYPE B FULL DEPTH		99 CY
CONC PVMT REPAIR TYPE C FULL DEPTH		248 CY
MEMBRANE WATERPROOFING		926 SY
HYDRATED LIME FOR ASPHALT MIXTURES		292 TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC		5 TON
FOUNDATION COURSE REPLACEMENT		9 CY
ASPH CONC FOR ST MAINT PTCHING, TYPE SPR		500 TON
ASPH CONC, TYPE SPR		29,000 TON
PLACE ASPH CONC FOR DRIVE & INTER		4,060 SY
ASPH CONCRETE FOR PATCHING, TYPE SPR		200 TON
PERF GRAD BIND (64-34)FOR ST MAINT PATCH		19 TON
PERF GRADED BINDER (64-34)		1,109 TON
PREP OF INTER & DRIVE		574 SY
TACK COAT		30,430 GAL
WATER		134 MGAL
EARTH SHOULDER CONSTRUCTION		492 STA
SUBGRADE PREPARATION		188 SY
COLD MILLING, CLASS 3		332 STA
COLD MILLING, CLASS 4		928 SY
COLD MILLING, CLASS 3		18 STA
TYPE A		
COLD MILLING, CLASS 3		27 STA
TYPE B		
SURFACE UNDER GUARDRAIL		950 SY

ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
SEEDING, TYPE B		8 ACRE
EROSION CONTROL, CLASS 1D	2,627	SY
FABRIC SILT FENCE-LOW POROSITY		855 LF
MULCH		18 TON

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	23,405	BDAY
BARRICADE, TYPE III	2,072	BDAY
TEMPORARY SIGN DAY	1,190	EACH
SIGN DAY	13,200	EACH
OVERLAY BROKEN LINES	1,329	STA
OVERLAY SOLID LINES	2,659	STA
FLAGGING	170	DAY
FURNISHING AND OPERATING PILOT VEHICLE	80	DAY
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED	75	HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	60	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	75	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	75	HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	15	HOUR
TEMPORARY SILT FENCE	500	LF
TEMPORARY MULCH	4	TON