

NOTICE TO CONTRACTORS

CALL ORDER 110
 FEDERAL PROJECT NO. IM-80-8(149)
 LOCATION: I-80, GOEHNER WEST
 COUNTIES: SEWARD

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on May 12, 2011. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS
 START DATE 08/01/2011 WORKING DAYS 50
 Price Range \$ 500,000 to \$ 2,000,000
 THIS PROJECT CONTAINS A DBE GOAL OF 5.0 %

Plans and specifications may be seen beginning April 19, 2011 at the Lincoln Central Office and April 25, 2011 at the District Engineer's Office at LINCOLN
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.
 This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	14	SHEETS	\$	3.50
STANDARD PLANS	5	SHEETS	\$	1.25

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T5	TYPICAL CROSS SECTIONS
2-S1 - 2-S3	SUMMARY OF QUANTITIES
2-N1	GENERAL INFORMATION
2-N2 - 2-N3	GENERAL INFORMATION--MILLED RUMBLE STRIPS
3	TYPICAL TRAFFIC CONTROL PLAN--TYPICAL LANE CLOSURE (FREEWAY-INTERSTATE)
4	TEMPORARY PAVEMENT MARKING PLAN

STANDARD PLANS

502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	13,500	B	DAY
BARRICADE, TYPE III	540	B	DAY
TEMPORARY SIGN DAY	280	E	EACH
SIGN DAY	4,752	E	EACH
OVERLAY BROKEN LINES	258	S	TA
OVERLAY SOLID LINES	516	S	TA
FLASHING ARROW PANEL	90	D	AY
FLAGGING	40	D	AY
TRAFFIC CONTROL MANAGEMENT	90	D	AY
FIELD OFFICE	1	E	EACH
MOBILIZATION	LUMP	L	LUMP
CONC PVMT REPAIR TYPE A FULL DEPTH	1	C	CY
CONC PVMT REPAIR TYPE B FULL DEPTH	9	C	CY
CONC PVMT REPAIR TYPE C FULL DEPTH	52	C	CY
CONC PVMT REPAIR TYPE A PARTIAL DEPTH	1	C	CY
CONC PVMT, PR-3500	465	C	CY
JOINT REPAIR			

HYDRATED LIME FOR ASPHALT MIXTURES	57 TON
FOUNDATION COURSE REPLACEMENT	11 CY
GRANULAR SUBDRAIN	124 EACH
ASPH CONC, TYPE SPS	1,600 TON
ASPH CONC, TYPE SP5(0.5)	4,310 TON
ASPH CONC, TYPE LC	1,390 TON
ASPH CONCRETE FOR PATCHING, TYPE SPS	100 TON
PERF GRADED BINDER (70-28)	321 TON
PERF GRADED BINDER (52-34)	85 TON
TACK COAT	8,330 GAL
RENTAL OF LOADER, FULLY OPERATED	15 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	10 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	15 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	15 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	5 HOUR
WATER	43 MGAL
EARTH SHOULDER CONSTRUCTION	172 STA
MILLING FOR ASPH CONC INLAY	4 EACH
RUMBLE STRIPS, ASPHALT	172 STA
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP LUMP
SEEDING, TYPE B	6 ACRE
TEMPORARY SILT FENCE	500 LF
MULCH	14 TON