

NOTICE TO CONTRACTORS

CALL ORDER 400
 FEDERAL PROJECT NO. STP-6-5(113)
 LOCATION: US-6, GRAFTON WEST
 COUNTIES: FILLMORE

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on June 16, 2011. At that time the bids will be opened and read for CULV BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CULVERTS

START DATE 08/15/2011 WORKING DAYS 45
 Price Range \$ 0 to \$ 500,000
 THIS PROJECT CONTAINS A DBE GOAL OF 5.0 %

Plans and specifications may be seen beginning May 24, 2011 at the Lincoln Central Office and May 31, 2011 at the District Engineer's Office at GRAND ISLAND

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	27	SHEETS	\$	6.75
CROSS SECTIONS (SHEETS X1 THRU X2)	2	SHEETS	\$	0.50
STANDARD PLANS	18	SHEETS	\$	4.50

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-W	WETLANDS
2-H1 - 2-H2	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
2-P1 - 2-P6	PHASING PLANS
2-L	EROSION CONTROL
3	PLAN & PROFILE SHEET
4 - 5	TRAFFIC CONTROL PLAN
6	TYPICAL TRAFFIC SIGNAL CONTROL PLAN FOR NARROW BRIDGE, ONE LANE, TWO WAY OPERATION WITH BARRIERS (10')
7	TEMPORARY TRAFFIC SIGNAL
8	TEMPORARY PAVEMENT MARKING PLAN
9	EARTHWORK DATA SHEET
10	DRAINAGE STRUCTURE CROSS SECTION--CULVERT CROSS SECTION
11 - 12	SPECIAL PLAN 1C 8' X 5' TRIPLE SPAN RC BOX CULVERT STA. 225+57.30
13 - 14	SPECIAL PLAN 2C CONCRETE PROTECTION BARRIER
R1	RIGHT-OF-WAY SHEET
X1 - X2	CROSS SECTIONS

STANDARD PLANS

301-R10	(3 SHEETS) PAVEMENT DETAILS
329-R8	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
805	R.O.W. POST
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 4 CULVERTS AT STA. 225+57.30

MOBILIZATION	LUMP	LUMP
REMOVE STRUCTURE		1 EACH
AT STA. 225+57.30		
EXCAVATION FOR BOX CULVERTS		860 CY
TEMPORARY SHORING	LUMP	LUMP
47B-3000 CONC FOR BOX CULV		178 CY
RE-STEEL FOR BOX CULVERT		15,802 LB

GROUP 9 BITUMINOUS

MOBILIZATION	LUMP	LUMP
RIGHT-OF-WAY POST		6 EACH
EARTHWORK MEASURED IN EMBANKMENT		192 CY
REMOVE PAVEMENT		688 SY
8" DOWELED CONCRETE BASE COURSE		175 SY
HYDRATED LIME FOR ASPHALT MIXTURES		4 TON
ASPH CONC, TYPE SP4(0.5)		330 TON
PERF GRADED BINDER (64-34)		16 TON
TACK COAT		110 GAL
WATER		3 MGAL
EARTH SHOULDER CONSTRUCTION		5 STA
SUBGRADE PREPARATION		688 SY
EROSION CONTROL, CLASS 1D		1,009 SY
FABRIC SILT FENCE-LOW POROSITY		473 LF

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II		784 BDAY
BARRICADE, TYPE III		332 BDAY
SIGN DAY		3,984 EACH
PAVEMENT MARKING REMOVAL		4,000 LF
TEMP PVMT MARKING, TYPE PAINT		4,500 LF
TEMP PVMT MARKING SURF PREP		2,000 LF
FLAGGING		12 DAY
CONCRETE PROTECTION BARRIER		450 LF
RELOCATE CONC PROTECTION BARRIER		425 LF
TEMPORARY RUMBLE STRIP		4 EACH
TEMPORARY TRAFFIC SIGNAL		1 EACH
TRAFFIC CONTROL MANAGEMENT		83 DAY
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED		10 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED		10 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED		10 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.		10 HOUR
TEMPORARY SILT FENCE		200 LF