

# NOTICE TO CONTRACTORS

CALL ORDER 300  
STATE PROJECT NO. RD-75-4(1009)  
LOCATION: US-75, HOMER-DAKOTA CITY  
COUNTIES: DAKOTA

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on August 25, 2011. At that time the bids will be opened and read for BR GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 5.4 MILES  
START DATE 07/09/2012 WORKING DAYS 65  
Price Range \$ 1,000,000 to \$ 3,000,000

Plans and specifications may be seen beginning August 02, 2011 at the Lincoln Central Office and August 08, 2011 at the District Engineer's Office at NORFOLK  
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

|                                 |           |    |      |
|---------------------------------|-----------|----|------|
| INFORMATIONAL PROPOSAL          | EACH      | \$ | 5.00 |
| PLANS (NOT INCLUDING STANDARDS) | 39 SHEETS | \$ | 9.75 |
| STANDARD PLANS                  | 9 SHEETS  | \$ | 2.25 |

## SHEET NO.

|             |   |
|-------------|---|
| 1           | TITLE PAGE  |
| 2-T1 - 2-T3 | TYPICAL CROSS SECTIONS  |
| 2-S1 - 2-S3 | SUMMARY OF QUANTITIES   |
| 2-W1 - 2-W6 | WETLANDS  |
| 2-H         | HORIZONTAL ALIGNMENT & ORIENTATION  |
| 2-N1 - 2-N2 | GENERAL INFORMATION--MILLED RUMBLE STRIPS   |
| 3 - 8       | PLAN SHEETS   |
| 9           | TYPICAL TRAFFIC SIGNAL CONTROL PLAN FOR TWO LANE, TWO WAY OPERATION WITH BARRIERS |
| 10          | TYPICAL TRAFFIC CONTROL PLAN--INERTIAL BARRIER SYSTEM                             |
| 11          | TEMPORARY PAVEMENT MARKING PLAN   |
| 12 - 16     | SPECIAL PLAN 1 STEEL GIRDER BRIDGE--CONCRETE REPAIR STA. 1413+54.77               |
| 17 - 23     | SPECIAL PLAN 1C GUARDRAIL PLAN  |
| 24 - 25     | SPECIAL PLAN 2C CONCRETE PROTECTION BARRIER                                       |

## STANDARD PLANS

|        |  |
|--------|--|
| 309    | MAILBOX SUPPORT POST                                     |
| 501-R5 | (3 SHEETS) EROSION CONTROL                               |
| 502    | SILT FENCE DETAILS                                       |
| 920-R5 | (2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE |
| 922-R8 | (2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING         |

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

## GROUP 6 BRIDGE AT STA. 1413+54.77

|                           |        |        |
|---------------------------|--------|--------|
| MOBILIZATION              | LUMP   | LUMP   |
| CLASS II REPAIR           |        | 15 SY  |
| CLASS III REPAIR          |        | 5 SY   |
| 47BD-4000 CONC FOR BRIDGE |        | 5 CY   |
| PREP BRIDGE               |        | 1 EACH |
| 1413+54.77                |        |        |
| EPOXY COATED RE-STEEL     | 535 LB |        |
| CONCRETE REPAIR           | 80 SF  |        |

# GROUP 7 GUARDRAIL

|                                  |      |      |
|----------------------------------|------|------|
| MOBILIZATION                     | LUMP | LUMP |
| W-BEAM GUARDRAIL                 | 287  | LF   |
| BRIDGE APPROACH SECTIONS         | 4    | EACH |
| GUARDRAIL END TREATMENT, TYPE II | 4    | EACH |

# GROUP 9 BITUMINOUS

|  |        |      |
|--|--------|------|
| OVERLAY BROKEN LINES                     | 861    | STA  |
| OVERLAY SOLID LINES                      | 1,722  | STA  |
| MOBILIZATION                             | LUMP   | LUMP |
| CRUSHED ROCK SURFACE COURSE              | 150    | CY   |
| MAILBOX POST                             | 6      | EACH |
| CONC PVMT REPAIR TYPE B FULL DEPTH       | 527    | CY   |
| CONC PVMT REPAIR TYPE C FULL DEPTH       | 336    | CY   |
| REMOVE GUARDRAIL                         | 612    | LF   |
| HYDRATED LIME FOR ASPHALT MIXTURES       | 127    | TON  |
| HYD LIME FOR ASPH MIXES FOR ST MAIN PATC | 1      | TON  |
| FOUNDATION COURSE REPLACEMENT            | 15     | CY   |
| ASPH CONC ST MAINT PATCH TYPE SP4 (0.5)  | 100    | TON  |
| ASPH CONC, TYPE SPS                      | 4,800  | TON  |
| ASPH CONC, TYPE SP4(0.5)                 | 12,410 | TON  |
| PLACE ASPH CONC FOR DRIVE & INTER        | 5,953  | SY   |
| ASPH CONCRETE FOR PATCHING, TYPE SPS     | 500    | TON  |
| ASPH CONC FOR PATCHING, TYPE SP4(0.5)    | 300    | TON  |
| PERF GRAD BIND (64-34)FOR ST MAINT PATCH | 4      | TON  |
| PERF GRADED BINDER (52-34)               | 201    | TON  |
| PERF GRADED BINDER (64-34)               | 610    | TON  |
| PREP OF INTER & DRIVE                    | 399    | SY   |
| TACK COAT                                | 23,990 | GAL  |
| COLD MILLING, CLASS 3                    | 289    | STA  |
| COLD MILLING, CLASS 5                    | 5,953  | SY   |
| COLD MILLING, CLASS 3                    | 578    | STA  |
| TYPE A                                   |        |      |
| RUMBLE STRIPS, ASPHALT 8"                | 574    | STA  |
| SURFACE UNDER GUARDRAIL                  | 280    | SY   |
| RAP INCENTIVE PAYMENT                    | 30,620 | EACH |
| ASPH PVMT SMOOTHNESS TESTING I/D         | LUMP   | LUMP |
| EROSION CONTROL, CLASS 1D                | 480    | SY   |

# GROUP 10 GENERAL ITEMS

|  |        |       |
|--|--------|-------|
| BARRICADE, TYPE II                     | 14,850 | B DAY |
| BARRICADE, TYPE III                    | 444    | B DAY |
| TEMPORARY SIGN DAY                     | 910    | EACH  |
| SIGN DAY                               | 8,669  | EACH  |
| TEMP PAVEMENT MARKING REMOVAL          | 9,000  | LF    |
| PAVEMENT MARKING REMOVAL               | 2,600  | LF    |
| TEMP PVMT MARKING, TYPE PAINT          | 9,000  | LF    |
| TEMP PVMT MARKING SURF PREP            | 9,000  | LF    |
| FLAGGING                               | 130    | DAY   |
| FURNISHING AND OPERATING PILOT VEHICLE | 60     | DAY   |
| CONCRETE PROTECTION BARRIER            | 800    | LF    |
| RELOCATE CONC PROTECTION BARRIER       | 800    | LF    |
| RELOC INERTIAL BARRIER SYSTEM          | 2      | EACH  |
| INERTIAL BARRIER SYSTEM                | 2      | EACH  |
| REPLACEMENT MODULE                     | 14     | EACH  |
| FIELD OFFICE                           | 1      | EACH  |
| MOBILIZATION                           | LUMP   | LUMP  |
| RENTAL OF LOADER, FULLY OPERATED       | 70     | HOUR  |
| RENTAL OF MOTOR GRADER, FULLY OPERATED | 60     | HOUR  |
| RENTAL OF DUMP TRUCK, FULLY OPERATED   | 70     | HOUR  |
| RENTAL OF SKID LOADER, FULLY OPERATED  | 70     | HOUR  |
| RENT CRAWLER MNTED HYD EXCAVATOR, F.O. | 10     | HOUR  |
| TEMPORARY SILT FENCE                   | 1,000  | LF    |