

NOTICE TO CONTRACTORS

CALL ORDER 810
FEDERAL PROJECT NO. NH-20-2(138)
LOCATION: US-20, CROOKSTON - VALENTINE
COUNTIES: CHERRY

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on September 29, 2011. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 10.6 MILES
START DATE 07/02/2012 WORKING DAYS 70
Price Range \$ 3,000,000 to \$ 6,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 2.0 %

Plans and specifications may be seen beginning September 06, 2011 at the Lincoln Central Office and September 12, 2011 at the District Engineer's Office at AINSWORTH
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	6 SHEETS	\$	1.50
STANDARD PLANS	4 SHEETS	\$	1.00

SHEET NO.

1	TITLE PAGE
2-S	SUMMARY OF QUANTITIES & TYPICAL CROSS SECTIONS
2-N1 - 2-N2	GENERAL INFORMATION--MILLED RUMBLE STRIPS
3	TEMPORARY PAVEMENT MARKING PLAN
4	TYPICAL PAVEMENT MARKING PLAN--5" PAVEMENT MARKING

STANDARD PLANS

920-R5	(2 SHEETS)	TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS)	TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	28,600	B DAY
BARRICADE, TYPE III	472	B DAY
TEMPORARY SIGN DAY	980	EACH
SIGN DAY	12,850	EACH
OVERLAY BROKEN LINES	1,686	STA
OVERLAY SOLID LINES	3,372	STA
PERMANENT PAVEMENT MARKING PAINT	141,300	LF
FLAGGING	140	DAY
FURNISHING AND OPERATING PILOT VEHICLE	65	DAY
TRAINING	500	HOUR
MOBILIZATION	LUMP	LUMP

GROUP 9 BITUMINOUS

HYDRATED LIME FOR ASPHALT MIXTURES	410 TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	4 TON
ASP CON ST MAIN PTCH TYPE SP4 SPEC(0.5)	400 TON
ASPH CONC, TYPE SPS	10,940 TON
ASPH CONC, TYPE SP4 SPECIAL(0.5)	16,230 TON
ASPH CONC, TYPE SPR	24,450 TON
ASPH CONCRETE FOR PATCHING, TYPE SPR	400 TON
PERF GRAD BIND (64-34)FOR ST MAINT PATCH	19 TON
PERF GRADED BINDER (52-34)	415 TON
PERF GRADED BINDER (64-34)	1,727 TON
TACK COAT	46,110 GAL
RENTAL OF LOADER, FULLY OPERATED	50 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	50 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	50 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	50 HOUR
COLD MILLING, CLASS 3	561 STA
COLD MILLING, CLASS 3	1,125 STA
TYPE A	
RUMBLE STRIPS, ASPHALT	1,115 STA
RAP INCENTIVE PAYMENT	89,114 EACH
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP LUMP