

NOTICE TO CONTRACTORS

CALL ORDER 100
FEDERAL PROJECT NO. STP-BR-63-2(114)
LOCATION: N-63, ALVO NORTH BRIDGES
COUNTIES: CASS

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on November 03, 2011. At that time the bids will be opened and read for GRAD CULV

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CULVERTS

START DATE 07/02/2012 WORKING DAYS 70
Price Range \$ 250,000 to \$ 1,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 7.0 %

Plans and specifications may be seen beginning October 11, 2011 at the Lincoln Central Office and October 17, 2011 at the District Engineer's Office at LINCOLN

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	45	SHEETS	\$	11.25
CROSS SECTIONS (SHEETS X1 THRU X42)	42	SHEETS	\$	10.50
STANDARD PLANS	14	SHEETS	\$	3.50

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-K	SUMMARY OF SOILS & GEOTECHNICAL INFORMATION
2-W1 - 2-W2	WETLANDS
2-H1 - 2-H6	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
3 - 6	PLAN & PROFILE SHEETS
7 - 8	PLAN SHEETS--EROSION CONTROL
9	TYPICAL TRAFFIC CONTROL PLAN--CONCRETE BARRIER PLACEMENT
10	TYPICAL TRAFFIC SIGNAL CONTROL PLAN FOR ONE LANE, TWO WAY OPERATION WITH BARRIERS
11	TEMPORARY TRAFFIC SIGNAL
12	TEMPORARY PAVEMENT MARKING PLAN
13 - 15	EARTHWORK DATA SHEETS
16 - 19	DRAINAGE STRUCTURE CROSS SECTIONS
20 - 21	SPECIAL PLAN 1C 9' X 9' TWIN SPAN RC BOX CULVERT STA. 240+20.50
22 - 23	SPECIAL PLAN 2C 12' X 8' TWIN SPAN RC BOX CULVERT STA. 318+48.50
24 - 25	SPECIAL PLAN 3C CONCRETE HEADWALL (FOR 36" - 60" CORRUGATED METAL PIPES WITH NO SKEW)
26	SPECIAL PLAN 4C CONCRETE HEADWALL (FOR 12" - 30" CORRUGATED METAL PIPES WITH NO SKEW)
27	SPECIAL PLAN 5C CONCRETE HEADWALL (FOR 36" - 60" CORRUGATED METAL PIPES WITH NO SKEW)
28	SPECIAL PLAN 6C EROSION CHECKS (ALL TYPES) & FABRIC SILT CHECKS
29 - 30	SPECIAL PLAN 7C TEMPORARY SILT CHECKS
31 - 32	SPECIAL PLAN 8C CONCRETE PROTECTION BARRIER
R1 - R2	RIGHT-OF-WAY SHEETS
X1 - X42	CROSS SECTIONS

STANDARD PLANS

329-R9	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
425-R4	COLLARS AND ELBOWS FOR CONCRETE PIPES
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
804	PRECAST CONCRETE R.O.W. MARKER
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION	3,585	CY
EXCAVATION, BORROW	3,030	CY
WATER	22	MGAL
RIGHT-OF-WAY MARKERS	10	EACH
REMOVE ASPHALT SURFACE	150	SY
24" DRIVE PIPE 2,3,4,5,6,7 OR 8	88	LF
GRAVEL SURFACE COURSE	5	TON
8" DOWELED CONC PAVE, CLASS 47B-3500	294	SY
TEMPORARY SURFACING	1,422	SY
8"		
STABILIZED SUBGRADE	294	SY
TYPE FLY ASH		
EARTH SHOULDER CONSTRUCTION	2	STA
FLY ASH	9	TON
COVER CROP SEEDING	1	ACRE
EROSION CONTROL, CLASS 1D	7,927	SY
EROSION CONTROL, CLASS 2A	692	SY
EROSION CHECKS, TYPE 1D	66	BALE
EROSION CHECKS, TYPE 2A	60	BALE
FABRIC SILT FENCE-LOW POROSITY	1,255	LF

GROUP 4 CULVERT AT STA. 240+20.50

MOBILIZATION	LUMP	LUMP
REMOVAL OF UNSUITABLE MATERIAL	158	CY
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	51	CY
EXCAVATION FOR BOX CULVERTS	423	CY
TEMPORARY SHORING	LUMP	LUMP
47B-3000 CONC FOR HDWL	1	CY
47B-3000 CONC FOR BOX CULV	245	CY
RE-STEEL FOR HEADWALL	270	LB
RE-STEEL FOR BOX CULVERT	22,136	LB
REMOVE STRUCTURE	1	EACH
AT STA. 240+20.50		
GRANULAR BACKFILL	198	TON
24" CULV PIPE 3,4,5,6	40	LF
36" CULV PIPE 3,4,5,6	30	LF

GROUP 4A CULVERT AT STA. 318+48.50

MOBILIZATION	LUMP	LUMP
REMOVAL OF UNSUITABLE MATERIAL	174	CY
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	87	CY
EXCAVATION FOR BOX CULVERTS	428	CY
TEMPORARY SHORING	LUMP	LUMP
47B-3000 CONC FOR HDWL	6	CY
47B-3000 CONC FOR BOX CULV	299	CY
RE-STEEL FOR HEADWALL	982	LB
RE-STEEL FOR BOX CULVERT	22,384	LB

REMOVE STRUCTURE	1 EACH
AT STA. 318+52.22	
GRANULAR BACKFILL	218 TON
48" CULV PIPE 3,4,5	58 LF
24" CULV PIPE 3,4,5,6	34 LF

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	1,880 BDAY
BARRICADE, TYPE III	1,410 BDAY
SIGN DAY	7,730 EACH
CONTRACTOR FURNISHED SIGN DAY	360 EACH
TEMP PAVEMENT MARKING REMOVAL	5,400 LF
PAVEMENT MARKING REMOVAL	4,400 LF
TEMP PVMT MARKING, TYPE PAINT	9,200 LF
TEMP PVMT MARKING SURF PREP	5,400 LF
FLAGGING	10 DAY
CONCRETE PROTECTION BARRIER	1,225 LF
RELOCATE CONC PROTECTION BARRIER	475 LF
TEMPORARY RUMBLE STRIP	8 EACH
TEMPORARY TRAFFIC SIGNAL	2 EACH
TRAFFIC CONTROL MANAGEMENT	125 DAY
FIELD OFFICE	1 EACH
MOBILIZATION	LUMP LUMP
RENTAL OF LOADER, FULLY OPERATED	20 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	20 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	20 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	20 HOUR
TEMPORARY SILT CHECK	200 LF
TEMPORARY SILT FENCE	500 LF
TEMPORARY MULCH	1 TON