

NOTICE TO CONTRACTORS

CALL ORDER 300
 FEDERAL PROJECT NO. STP-24-6(102)
 LOCATION: N-24, NORFOLK-STANTON
 COUNTIES: MADISON
 STANTON

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on November 03, 2011 . At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 9.0 MILES
 START DATE 04/02/2012 WORKING DAYS 130
 Price Range \$ 3,000,000 to \$ 6,000,000
 THIS PROJECT CONTAINS A DBE GOAL OF 4.0 %

Plans and specifications may be seen beginning October 11, 2011 at the Lincoln Central Office and October 17, 2011 at the District Engineer's Office at NORFOLK Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING OR STANDARDS)	47 SHEETS	\$	11.75
STANDARD PLANS	11 SHEETS	\$	2.75

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T7	TYPICAL CROSS SECTIONS
2-S1 - 2-S5	SUMMARY OF QUANTITIES
2-A1 - 2-A9	PHOTO MAPS
2-H	HORIZONTAL ALIGNMENT & ORIENTATION
2-N1	GENERAL INFORMATION
2-N2 - 2-N3	GENERAL INFORMATION--MILLED RUMBLE STRIPS
3 - 11	PLAN SHEETS
12	TEMPORARY TRAFFIC SIGNAL
13	TYPICAL TRAFFIC SIGNAL CONTROL PLAN--ONE LANE, TWO WAY OPERATION WITHOUT BARRIERS
14	TEMPORARY PAVEMENT MARKING PLAN
15	SPECIAL PLAN 1C PAVEMENT APPROACH REPAIR REF. POST NO. 6+59 REF. POST NO. 8+53
16 - 23	SPECIAL PLAN 2C GUARDRAIL PLAN

STANDARD PLANS

108-R4	SUPERELEVATION PLAN FOR CONCRETE AND BITUMINOUS SURFACING
309	MAILBOX SUPPORT POST
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
901-R9	HIGHWAY DELINEATORS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	21,080	B	DAY
BARRICADE, TYPE III	968	B	DAY
TEMPORARY SIGN DAY	960	E	EACH
SIGN DAY	15,288	E	EACH
OVERLAY BROKEN LINES	1,424	S	TA
OVERLAY SOLID LINES	2,848	S	TA
FLAGGING	280	D	DAY
FURNISHING AND OPERATING PILOT VEHICLE	140	D	DAY
TEMPORARY RUMBLE STRIP	8	E	EACH
TEMPORARY TRAFFIC SIGNAL	2	E	EACH
FIELD OFFICE	1	E	EACH
TRAINING	1,000	H	HOUR
MOBILIZATION	LUMP	L	LUMP
DELINEATOR, TYPE III	79	E	EACH
INSTALL CHEVRONS	16	E	EACH
REMOVE DELINEATOR UNITS	80	E	EACH
ROADWAY GRADING	10	S	TA
REMOVE ASPH SURF FROM PAVEMENT	5,984	S	Y
GRAVEL SURFACE COURSE	140	C	Y
CRUSHED ROCK SURFACE COURSE	115	C	Y
MAILBOX POST	19	E	EACH
CONC PVMT REPAIR TYPE A FULL DEPTH	18	C	Y
CONC PVMT REPAIR TYPE B FULL DEPTH	95	C	Y
CONC PVMT REPAIR TYPE C FULL DEPTH	564	C	Y
CONC PVMT REPAIR TYPE A PARTIAL DEPTH	1	C	Y
CONC PVMT, PR-3500	648	C	Y
JOINT REPAIR			
BRIDGE APPROACH REPAIR	2	C	Y
W-BEAM GUARDRAIL	400	L	F
REMOVE GUARDRAIL	900	L	F
BRIDGE APPROACH SECTIONS	8	E	EACH
GUARDRAIL END TREATMENT, TYPE II	8	E	EACH
HYDRATED LIME FOR ASPHALT MIXTURES	285	T	ON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	5	T	ON
FOUNDATION COURSE REPLACEMENT	49	C	Y
GRANULAR SUBDRAIN	76	E	EACH
ASPH CONC FOR ST MAINT PTCHING, TYPE SPR	500	T	ON
ASPH CONC, TYPE SPS	14,550	T	ON
ASPH CONC, TYPE LC	6,830	T	ON
ASPH CONC, TYPE SPR	21,590	T	ON
PLACE ASPH CONC FOR DRIVE & INTER	2,868	S	Y
ASPH CONCRETE FOR PATCHING, TYPE SPS	500	T	ON
PERF GRAD BIND (64-28)FOR ST MAINT PATCH	25	T	ON
PERF GRADED BINDER (70-34)	579	T	ON
PERF GRADED BINDER (52-34)	752	T	ON
PERF GRADED BINDER (64-34)	1,079	T	ON
TACK COAT	44,600	G	GAL
RENTAL OF LOADER, FULLY OPERATED	60	H	HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	50	H	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	60	H	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	60	H	HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	10	H	HOUR
WATER	240	M	MGAL
CRACKING & SEATING CONC PVMT	127,589	S	Y
EARTH SHOULDER CONSTRUCTION	956	S	TA
MILLING CONC FOR INLAYS	7	E	EACH
RUMBLE STRIPS, ASPHALT	908	S	TA
SURFACE UNDER GUARDRAIL	860	S	Y
RAP INCENTIVE PAYMENT	46,533	E	EACH
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	L	LUMP
SEEDING, TYPE B	18	A	ACRE
EROSION CONTROL, CLASS 1D	3,692	S	Y
TEMPORARY SILT FENCE	1,000	L	F
MULCH	41	T	TON