

NOTICE TO CONTRACTORS

CALL ORDER 650  
 FEDERAL PROJECT NO. NH-83-2(138)  
 LOCATION: US-83, NORTH PLATTE NORTH  
 COUNTIES: LINCOLN

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on November 17, 2011. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 5.3 MILES  
 START DATE 08/06/2012 WORKING DAYS 50  
 Price Range \$ 500,000 to \$ 2,000,000  
 THIS PROJECT CONTAINS A DBE GOAL OF 2.0 %

Plans and specifications may be seen beginning October 25, 2011 at the Lincoln Central Office and October 31, 2011 at the District Engineer's Office at NORTH PLATTE. Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	22	SHEETS	\$	5.50
STANDARD PLANS	5	SHEETS	\$	1.25

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T2	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-A1 - 2-A6	PHOTO MAPS
2-H1 - 2-H2	HORIZONTAL ALIGNMENT & ORIENTATION
2-N1	GENERAL INFORMATION
2-N2 - 2-N3	GENERAL INFORMATION--MILLED RUMBLE STRIPS
3 - 8	PLAN SHEETS
9	TEMPORARY PAVEMENT MARKING PLAN

STANDARD PLANS

309	MAILBOX SUPPORT POST
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	7,500	BDAY
BARRICADE, TYPE III	360	BDAY
TEMPORARY SIGN DAY	700	EACH
SIGN DAY	6,237	EACH
OVERLAY BROKEN LINES	696	STA
OVERLAY SOLID LINES	1,392	STA
FLAGGING	100	DAY
FURNISHING AND OPERATING PILOT VEHICLE	50	DAY
FIELD OFFICE	1	EACH
MOBILIZATION	LUMP	LUMP
MAILBOX POST	21	EACH
HYDRATED LIME FOR ASPHALT MIXTURES	177	TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	5	TON
ASPH CONC ST MAINT PATCH TYPE SP4 (0.5)	500	TON
ASPH CONC, TYPE SPS	5,510	TON

GROUP 9 BITUMINOUS

ASPH CONC, TYPE SP4(0.5)	17,490 TON
PLACE ASPH CONC FOR DRIVE & INTER	6,540 SY
ASPH CONC FOR PATCHING, TYPE SP4(0.5)	200 TON
PERF GRAD BIND (64-34)FOR ST MAINT PATCH	24 TON
PERF GRADED BINDER (52-34)	209 TON
PERF GRADED BINDER (64-34)	849 TON
TACK COAT	24,040 GAL
FOG SEAL	90 GAL
RENTAL OF LOADER, FULLY OPERATED	20 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	20 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	20 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	20 HOUR
COLD MILLING, CLASS 3	206 STA
COLD MILLING, CLASS 3	91 STA
TYPE A	
COLD MILLING, CLASS 3	114 STA
TYPE B	
COLD MILLING, CLASS 3	503 STA
TYPE C	
RUMBLE STRIPS, ASPHALT	544 STA
RAP INCENTIVE PAYMENT	39,440 EACH
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP LUMP