

NOTICE TO CONTRACTORS

CALL ORDER 105
STATE PROJECT NO. RD-92-6(1015)
LOCATION: N-92, WAHOO WEST
COUNTIES: SAUNDERS

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on December 15, 2011 . At that time the bids will be opened and read for BR GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 4.0 MILES
START DATE 07/09/2012 WORKING DAYS 65
Price Range \$ 1,000,000 to \$ 3,000,000

Plans and specifications may be seen beginning November 22, 2011 at the Lincoln Central Office and November 28, 2011 at the District Engineer's Office at LINCOLN
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	42 SHEETS	\$	10.50
STANDARD PLANS	6 SHEETS	\$	1.50

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T4	TYPICAL CROSS SECTIONS
2-S1 - 2-S3	SUMMARY OF QUANTITIES
2-A1 - 2-A5	PHOTO MAPS
2-H1 - 2-H4	HORIZONTAL ALIGNMENT & CONTROL POINTS
2-N1 - 2-N2	GENERAL INFORMATION--MILLED RUMBLE STRIPS
3 - 7	PLAN SHEETS
8	TYPICAL TRAFFIC SIGNAL CONTROL PLAN FOR ONE LANE, TWO WAY OPERATION WITH BARRIERS @ STA. 395+00
9	TEMPORARY TRAFFIC SIGNAL
10	TEMPORARY PAVEMENT MARKING PLAN
11 - 13	SPECIAL PLAN 1C CONCRETE SLAB BRIDGE STA. 395+20.00
14 - 23	SPECIAL PLAN 2C GUARDRAIL PLAN
24 - 25	SPECIAL PLAN 3C CONCRETE PROTECTION BARRIER

STANDARD PLANS

920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 6 BRIDGE AT STA 395+20.00

MOBILIZATION	LUMP	LUMP
47BD-4000 CONC FOR BRIDGE		4 CY
EPOXY COATED RE-STEEL FOR CONC RAIL		605 LB
PREP BRIDGE		1 EACH
395+20		

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
CULV MOUNTED GDRL POST		4 EACH
W-BEAM GUARDRAIL		612 LF
REMOVE GUARDRAIL		692 LF

BRIDGE APPROACH SECTIONS	4 EACH
GUARDRAIL END TREATMENT, TYPE I	12 EACH

GROUP 9 BITUMINOUS

OVERLAY BROKEN LINES	758 STA
OVERLAY SOLID LINES	1,516 STA
MOBILIZATION	LUMP LUMP
GRAVEL SURFACE COURSE	150 TON
CONC PVMT REPAIR TYPE A FULL DEPTH	707 CY
CONC PVMT REPAIR TYPE B FULL DEPTH	210 CY
HYDRATED LIME FOR ASPHALT MIXTURES	152 TON
FOUNDATION COURSE REPLACEMENT	17 CY
ASPH CONC, TYPE SPS	4,240 TON
ASPH CONC, TYPE RLC	3,110 TON
ASPH CONC, TYPE SPR	11,870 TON
PLACE ASPH CONC FOR DRIVE & INTER	1,980 SY
ASPH CONCRETE FOR PATCHING, TYPE SPR	200 TON
PERF GRADED BINDER (52-34)	161 TON
PERF GRADED BINDER (64-34)	625 TON
TACK COAT	22,260 GAL
RENTAL OF LOADER, FULLY OPERATED	20 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	20 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	20 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	20 HOUR
COLD MILLING, CLASS 3	255 STA
COLD MILLING, CLASS 3	37,619 SY
TYPE A	
COLD MILLING, CLASS 5	1,980 SY
MILLING CONC FOR INLAYS	2 EACH
RUMBLE STRIPS, ASPHALT	426 STA
RUMBLE STRIPS, ASPHALT 8"	427 STA
SURFACE UNDER GUARDRAIL	732 SY
RAP INCENTIVE PAYMENT	33,014 EACH
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP LUMP

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	7,500 BDAY
BARRICADE, TYPE III	632 BDAY
TEMPORARY SIGN DAY	910 EACH
SIGN DAY	9,216 EACH
TEMP PAVEMENT MARKING REMOVAL	2,600 LF
PAVEMENT MARKING REMOVAL	1,650 LF
TEMP PVMT MARKING, TYPE PAINT	2,600 LF
FLAGGING	130 DAY
FURNISHING AND OPERATING PILOT VEHICLE	50 DAY
CONCRETE PROTECTION BARRIER	437 LF
RELOCATE CONC PROTECTION BARRIER	437 LF
TEMPORARY RUMBLE STRIP	4 EACH
TEMPORARY TRAFFIC SIGNAL	1 EACH
MOBILIZATION	LUMP LUMP