

NOTICE TO CONTRACTORS

CALL ORDER 110
STATE PROJECT NO. MISC-62-7(1006)
LOCATION: N-62, ELK CREEK EAST CULVERT
COUNTIES: JOHNSON

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on December 15, 2011 . At that time the bids will be opened and read for CULVERTS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CULVERTS

START DATE 09/10/2012 WORKING DAYS 40
Price Range \$ 0 to \$ 500,000

Plans and specifications may be seen beginning November 22, 2011 at the Lincoln Central Office and November 28, 2011 at the District Engineer's Office at LINCOLN

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	20	SHEETS	\$	5.00
CROSS SECTIONS (SHEETS X1 THRU X4)	4	SHEETS	\$	1.00
STANDARD PLANS	11	SHEETS	\$	2.75

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-W	WETLANDS
2-H1 - 2-H2	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
3	PLAN SHEET--REMOVAL/CONSTRUCTION/EROSION CONTROL
4	TYPICAL TRAFFIC CONTROL PLAN--TYPICAL YIELD CONTROL FOR LOW VOLUME, ONE LANE, TWO WAY TRAFFIC (CONCRETE PROTECTION BARRIERS)
5	TEMPORARY PAVEMENT MARKING PLAN
6	DRAINAGE STRUCTURE CROSS SECTION
7 - 9	SPECIAL PLAN 1C 10' X 14' TWIN SPAN RC BOX CULVERT STA. 171+16.00
10	SPECIAL PLAN 2C EROSION CHECKS (ALL TYPES) & FABRIC SILT CHECKS
11 - 12	SPECIAL PLAN 3C TEMPORARY SILT CHECKS
13 - 14	SPECIAL PLAN 4C CONCRETE PROTECTION BARRIER
R1	RIGHT-OF-WAY SHEET
X1 - X4	CROSS SECTIONS

STANDARD PLANS

403-R2	(2 SHEETS) BENDS AND BREAKS FOR CONCRETE BOX CULVERTS
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
804	PRECAST CONCRETE R.O.W. MARKER
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 4 CULVERTS AT STA. 171+16.00

BARRICADE, TYPE II	1,245	BDAY
BARRICADE, TYPE III	332	BDAY
SIGN DAY	2,490	EACH
TEMP PAVEMENT MARKING REMOVAL	2,420	LF
PAVEMENT MARKING REMOVAL	130	LF
TEMP PVMT MARKING, TYPE PAINT	2,420	LF
TEMP PVMT MARKING SURF PREP	2,420	LF
CONCRETE PROTECTION BARRIER	250	LF
MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL	1	EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER	7	MGAL
RIGHT-OF-WAY MARKERS	4	EACH
EARTHWORK MEASURED IN EMBANKMENT	809	CY
PREPARATION OF STRUCTURE	1	EACH
AT STA. 171+16.00		
EXCAVATION FOR BOX CULVERTS	163	CY
47B-3000 CONC FOR BOX CULV	135	CY
RE-STEEL FOR BOX CULVERT	10,521	LB
CRUSHED ROCK FOR BASE COURSE	31	CY
EROSION CONTROL, CLASS 1D	1,040	SY
EROSION CHECKS, TYPE WATTLE	185	LF
TEMPORARY SILT CHECK	100	LF
TEMPORARY SILT FENCE	100	LF