

NOTICE TO CONTRACTORS

CALL ORDER 210
STATE PROJECT NO. MISC-S13H(1003)
LOCATION: S13H, CEDAR CREEK EAST
COUNTIES: CASS

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on December 15, 2011 . At that time the bids will be opened and read for CONC PAVE CULV

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CONCRETE PAVEMENT CULVERTS
START DATE 09/10/2012 WORKING DAYS 40
Price Range \$ 0 to \$ 500,000

Plans and specifications may be seen beginning November 22, 2011 at the Lincoln Central Office and November 28, 2011 at the District Engineer's Office at OMAHA
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	26	SHEETS	\$	6.50
CROSS SECTIONS (SHEETS X1 THRU X2)	2	SHEETS	\$	0.50
STANDARD PLANS	16	SHEETS	\$	4.00

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-A	PHOTO MAP
2-H1 - 2-H2	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
2-P	PHASING PLANS
2-L	EROSION CONTROL
3	PLAN SHEET
4	TYPICAL TRAFFIC CONTROL PLAN--INERTIAL BARRIER SYSTEM
5	TEMPORARY PAVEMENT MARKING PLAN
6	PAVEMENT MARKING PLAN--WORK ZONE TRAFFIC CONTROL
7	EARTHWORK DATA SHEET
8 - 9	DRAINAGE STRUCTURE CROSS SECTIONS
10 - 13	SPECIAL PLAN 1C 6' X 4' TWIN SPAN RC BOX CULVERT STA. 1013+15.50
14	SPECIAL PLAN 2C EROSION CHECKS (ALL TYPES) & FABRIC SILT CHECKS
15 - 16	SPECIAL PLAN 3C TEMPORARY SILT CHECKS
17 - 18	SPECIAL PLAN 4C CONCRETE PROTECTION BARRIER
R1	RIGHT-OF-WAY SHEET
X1 - X2	CROSS SECTIONS

STANDARD PLANS

301-R10	(3 SHEETS) PAVEMENT DETAILS
329-R9	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
804	PRECAST CONCRETE R.O.W. MARKER
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 3 CONCRETE PAVEMENT

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)		558 CY
RIGHT-OF-WAY MARKERS		4 EACH
SAWING PAVEMENT		30 LF
REMOVE DRIVEWAY		22 SY
CONC 47B-3500 DRIVEWAY		22 SY
8" DOWELED CONC PAVE, CLASS 47B-3500		67 SY
TEMPORARY SURFACING		175 SY
8"		
EARTH SHOULDER CONSTRUCTION		1 STA
SUBGRADE PREPARATION		89 SY
EROSION CONTROL, CLASS 1D		1,274 SY
EROSION CHECKS, TYPE 1D		20 BALE

GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
REMOVE FLARED- END SECTION		2 EACH
REMOVE HEADWALLS FROM CULV		3 EACH
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL		129 CY
EXCAVATION FOR BOX CULVERTS		136 CY
TEMPORARY SHORING	LUMP	LUMP
AT STA. 1013+15.5		
47B-3000 CONC FOR BOX CULV		79 CY
RE-STEEL FOR BOX CULVERT		6,290 LB
CRUSHED ROCK FOR BASE COURSE		25 CY

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II		1,444 BDAY
BARRICADE, TYPE III		646 BDAY
SIGN DAY		2,584 EACH
CONTRACTOR FURNISHED SIGN DAY		76 EACH
TEMP PAVEMENT MARKING REMOVAL		1,800 LF
PAVEMENT MARKING REMOVAL		500 LF
TEMP PVMT MARKING, TYPE PAINT		2,200 LF
TEMP PVMT MARKING SURF PREP		1,800 LF
CONCRETE PROTECTION BARRIER		375 LF
RELOCATE CONC PROTECTION BARRIER		200 LF
INERTIAL BARRIER SYSTEM		1 EACH
REPLACEMENT MODULE		7 EACH
MOBILIZATION	LUMP	LUMP
TEMPORARY SILT CHECK		200 LF
TEMPORARY SILT FENCE		200 LF
TEMPORARY EARTH CHECK		200 LF