

NOTICE TO CONTRACTORS

CALL ORDER 500
STATE PROJECT NO. S-L17J(1010)
LOCATION: L17J, SIDNEY SOUTH
COUNTIES: CHEYENNE

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on February 02, 2012. At that time the bids will be opened and read for CONC PAVE, ELEC

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CONCRETE PAVEMENT
START DATE 06/04/2012 WORKING DAYS 50
Price Range \$ 250,000 to \$ 1,000,000

Plans and specifications may be seen beginning January 10, 2012 at the Lincoln Central Office and January 17, 2012 at the District Engineer's Office at GERING
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	112	SHEETS	\$	28.00
CROSS SECTIONS (SHEETS X1 THRU X11)	11	SHEETS	\$	2.75
STANDARD PLANS	15	SHEETS	\$	3.75

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T2	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-W	WETLANDS
2-H1 - 2-H3	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
2-P1 - 2-P42	PHASING PLANS--PHASE 1-6
2-L1 - 2-L2	GEOMETRICS
2-L3 - 2-L9	CONSTRUCTION & REMOVAL
3 - 4	PLAN & PROFILE SHEETS
5 - 40	TEMPORARY TRAFFIC CONTROL--PHASE 1-6
41 - 42	TEMPORARY TRAFFIC SIGNAL PLAN
43 - 46	TRAFFIC SIGNAL PLAN
47	TEMPORARY PAVEMENT MARKING PLAN
48 - 51	ROADWAY LIGHTING PLANS
52	EARTHWORK DATA SHEET
53 - 54	SPECIAL PLAN 1C TEMPORARY SILT CHECKS
X1 - X11	CROSS SECTIONS

STANDARD PLANS

301-R10	(3 SHEETS) PAVEMENT DETAILS
329-R9	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
502	SILT FENCE DETAILS
910-R2	SIGNAL FACE CONFIGURATION
914-R6	PULL BOX DETAIL
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
924	(3 SHEETS) TYPICAL URBAN TRAFFIC CONTROL PLAN

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 3 CONCRETE PAVEMENT

MOBILIZATION	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)		847 CY
REMOVE PAVEMENT		1,161 SY
SAWING PAVEMENT		186 LF
REMOVE ASPHALT SURFACE		11,247 SY

REMOVE CURB	1,014 LF
TIE BARS	192 EACH
CONC 47B-3500 CURB TYPE II	1,014 LF
CONC 47B-3000 MEDIAN SURFACING	2,100 SY
9" CONC PVMT, 47B-3500	1,765 SY
9" DOWELED CONC PVMT, 47B-3500	8,769 SY
TEMPORARY SURFACING	263 SY
10"	
FOUNDATION COURSE	10,534 SY
4"	
GRANULAR SUBDRAIN	20 EACH
SURFACING 10"	1,043 SY
WATER	43 MGAL
EARTH SHOULDER CONSTRUCTION	22 STA
SUBGRADE PREPARATION	11,577 SY
SEEDING, TYPE B	1 ACRE
MULCH	1 TON

GROUP 8B ELECTRICAL

TEMPORARY TRAFFIC SIGNAL	1 EACH
MOBILIZATION	LUMP
PULL BOX, TYPE PB-1	1 EACH
PULL BOX, TYPE PB-1A	4 EACH
PULL BOX, TYPE PB-2	1 EACH
PULL BOX, TYPE PB-2A	8 EACH
PULL BOX, TYPE PB-5	1 EACH
VEHICLE DETECTOR, TYPE A PREFORMED	8 EACH
VEHICLE DETECTOR, TYPE B PREFORMED	8 EACH
VEHICLE DETECTOR, TYPE TD-3	8 EACH
2" CONDUIT IN TRENCH	843 LF
2" CONDUIT UNDER ROADWAY	318 LF
2/C #14 AWG DETECTOR LEAD-IN CABLE	3,561 LF
STREET LIGHT CABLE, NO. 6 BARE	55 LF
STREET LIGHT CABLE, NO. 6 USE	110 LF
INST TRAF SIG CONTROLLER, TC-2070	1 EACH
REMOVE PEDESTAL POLE	2 EACH
REMOVE PULL BOX	7 EACH
REMOVE MAST ARM SIGNAL POLE	1 EACH
RELOCATE STREET LIGHTING UNIT	1 EACH

GROUP 10 GENERAL

BARRICADE, TYPE II	9,798 BDAY
BARRICADE, TYPE III	1,559 BDAY
SIGN DAY	1,666 EACH
CONTRACTOR FURNISHED SIGN DAY	1,050 EACH
TEMP PAVEMENT MARKING REMOVAL	28,700 LF
PAVEMENT MARKING REMOVAL	3,300 LF
TEMP PVMT MARKING, TYPE PAINT	35,800 LF
TEMP PVMT MARKING SURF PREP	26,800 LF
TUBULAR POST	80 EACH
CHANNELIZING BLOCK	140 EACH
FLASHING ARROW PANEL	69 DAY
FLAGGING	10 DAY
TRAFFIC CONTROL MANAGEMENT	76 DAY
FIELD OFFICE	1 EACH
MOBILIZATION	LUMP
CONSTRUCTION STAKING AND SURVEYING	LUMP
RENTAL OF LOADER, FULLY OPERATED	5 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	5 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	5 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	5 HOUR
TEMPORARY SILT CHECK	200 LF
TEMPORARY SILT FENCE	200 LF