

NOTICE TO CONTRACTORS

CALL ORDER 600
 FEDERAL PROJECT NO. STP-30-3(115)
 LOCATION: US-30, OVERTON EAST
 COUNTIES: DAWSON

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on February 02, 2012. At that time the bids will be opened and read for GRAD BR GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 6.1 MILES
 START DATE 07/30/2012 WORKING DAYS 55
 Price Range \$ 1,000,000 to \$ 3,000,000
 THIS PROJECT CONTAINS A DBE GOAL OF 4.0 %

Plans and specifications may be seen beginning January 10, 2012 at the Lincoln Central Office and January 17, 2012 at the District Engineer's Office at NORTH PLATTE
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

| | | | | |
|---|----|--------|----|------|
| INFORMATIONAL PROPOSAL | | EACH | \$ | 5.00 |
| PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS) | 39 | SHEETS | \$ | 9.75 |
| CROSS SECTIONS (SHEETS X1 THRU X4) | 4 | SHEETS | \$ | 1.00 |
| STANDARD PLANS | 15 | SHEETS | \$ | 3.75 |

SHEET NO.

| | |
|-------------|--|
| 1 | TITLE PAGE |
| 2-T1 - 2-T4 | TYPICAL CROSS SECTIONS |
| 2-S1 - 2-S2 | SUMMARY OF QUANTITIES |
| 2-W1 - 2-W6 | WETLANDS |
| 2-H1 - 2-H2 | HORIZONTAL ALIGNMENT & ORIENTATION |
| 2-N1 | GENERAL INFORMATION |
| 2-N2 - 2-N3 | GENERAL INFORMATION--MILLED RUMBLE STRIPS |
| 2-L | CONSTRUCTION & REMOVAL |
| 3 - 8 | PLAN SHEETS |
| 9 | TYPICAL TRAFFIC SIGNAL CONTROL PLAN--ONE LANE, TWO WAY OPERATION WITHOUT BARRIERS |
| 10 | TEMPORARY TRAFFIC SIGNAL |
| 11 | TEMPORARY PAVEMENT MARKING PLAN |
| 12 | PAVEMENT MARKING DETAILS |
| 13 | TYPICAL PAVEMENT MARKING PLAN--5" PAVEMENT MARKING |
| 14 | EARTHWORK DATA SHEET |
| 15 - 18 | SPECIAL PLAN 1 BRIDGE REPAIR STA. 98+47.00 |
| 19 - 22 | SPECIAL PLAN 1C GUARDRAIL PLAN |
| X1 - X4 | CROSS SECTIONS |

STANDARD PLANS

| | |
|--------|--|
| 303 | (2 SHEETS) CURB RAMP |
| 501-R5 | (3 SHEETS) EROSION CONTROL |
| 502 | SILT FENCE DETAILS |
| 920-R5 | (2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE |
| 921-R5 | (2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE |
| 922-R8 | (2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING |
| 924 | (3 SHEETS) TYPICAL URBAN TRAFFIC CONTROL PLAN |

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

| | | |
|----------------------------------|------|--------|
| MOBILIZATION | LUMP | LUMP |
| WATER | | 3 MGAL |
| EARTHWORK MEASURED IN EMBANKMENT | 111 | CY |
| REMOVE ASPHALT SURFACE | 240 | SY |
| REMOVE WALK | 16 | SY |
| REMOVE GUARDRAIL | 335 | LF |
| EROSION CONTROL, CLASS 1D | 859 | SY |

GROUP 6 BRIDGE AT STA. 98+47.00

| | | |
|---------------------------------------|------|------|
| MOBILIZATION | LUMP | LUMP |
| PREFORMED EXPANSION JOINT, TYPE B | 42 | LF |
| PRECOMPRESSED POLY FOAM JOINT, TYPE B | 42 | LF |
| PREP BRIDGE 98+47.00 | 1 | EACH |
| CONCRETE REPAIR | 45 | SF |

GROUP 7 GUARDRAIL

| | | |
|----------------------------------|------|------|
| MOBILIZATION | LUMP | LUMP |
| W-BEAM GUARDRAIL | 94 | LF |
| BRIDGE APPROACH SECTIONS | 4 | EACH |
| GUARDRAIL END TREATMENT, TYPE II | 4 | EACH |

GROUP 9 BITUMINOUS

| | | |
|---|--------|------|
| OVERLAY BROKEN LINES | 943 | STA |
| OVERLAY SOLID LINES | 1,092 | STA |
| MOBILIZATION | LUMP | LUMP |
| CONC 47B-3000 SIDEWALKS | 16 | SY |
| DETECTABLE WARNING PANEL | 20 | SF |
| CONC PVMT REPAIR TYPE A FULL DEPTH | 3 | CY |
| CONC PVMT REPAIR TYPE B FULL DEPTH | 251 | CY |
| CONC PVMT REPAIR TYPE C FULL DEPTH | 57 | CY |
| 24" WHT WET RFLC PRF PVMT MKNG T4 GVD | 54 | LF |
| HYDRATED LIME FOR ASPHALT MIXTURES | 186 | TON |
| HYD LIME FOR ASPH MIXES FOR ST MAIN PATC | 5 | TON |
| FOUNDATION COURSE REPLACEMENT | 6 | CY |
| ASPH CONC FOR ST MAINT PTCHING, TYPE SPR | 500 | TON |
| ASPH CONC, TYPE SPS | 6,210 | TON |
| ASPH CONC, TYPE SPR | 18,430 | TON |
| PLACE ASPH CONC FOR DRIVE & INTER | 2,788 | SY |
| ASPH CONCRETE FOR PATCHING, TYPE SPR | 200 | TON |
| PERF GRAD BIND (64-34) FOR ST MAINT PATCH | 19 | TON |
| PERF GRADED BINDER (52-34) | 235 | TON |
| PERF GRADED BINDER (64-34) | 707 | TON |
| TACK COAT | 25,700 | GAL |
| COLD MILLING, CLASS 3 | 305 | STA |
| COLD MILLING, CLASS 5 | 2,788 | SY |
| COLD MILLING, CLASS 3 TYPE A | 629 | STA |
| COLD MILLING, CLASS 3 TYPE B | 14 | STA |
| RUMBLE STRIPS, ASPHALT | 606 | STA |
| SURFACE UNDER GUARDRAIL | 270 | SY |
| RAP INCENTIVE PAYMENT | 42,228 | EACH |
| ASPH PVMT SMOOTHNESS TESTING I/D | LUMP | LUMP |

GROUP 10 GENERAL ITEMS

| | | |
|-------------------------------|--------|-------|
| BARRICADE, TYPE II | 10,000 | B DAY |
| BARRICADE, TYPE III | 868 | B DAY |
| TEMPORARY SIGN DAY | 770 | EACH |
| SIGN DAY | 8,749 | EACH |
| PAVEMENT MARKING REMOVAL | 3,500 | LF |
| TEMP PVMT MARKING, TYPE PAINT | 4,500 | LF |

| | |
|--|-----------|
| TEMP PVMT MARKING SURF PREP | 1,750 LF |
| FLAGGING | 110 DAY |
| FURNISHING AND OPERATING PILOT VEHICLE | 50 DAY |
| TEMPORARY RUMBLE STRIP | 4 EACH |
| TEMPORARY TRAFFIC SIGNAL | 1 EACH |
| FIELD OFFICE | 1 EACH |
| MOBILIZATION | LUMP LUMP |
| RENTAL OF LOADER, FULLY OPERATED | 35 HOUR |
| RENTAL OF MOTOR GRADER, FULLY OPERATED | 30 HOUR |
| RENTAL OF DUMP TRUCK, FULLY OPERATED | 35 HOUR |
| RENTAL OF SKID LOADER, FULLY OPERATED | 35 HOUR |
| RENT CRAWLER MNTED HYD EXCAVATOR, F.O. | 5 HOUR |
| TEMPORARY SILT FENCE | 200 LF |