

NOTICE TO CONTRACTORS

CALL ORDER 305
FEDERAL PROJECT NO. STPD-14-3(114)
LOCATION: N-14, ALBION-PETERSBURG
COUNTIES: BOONE

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on April 12, 2012. At that time the bids will be opened and read for GRAD BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 11.7 MILES
START DATE 06/11/2012 WORKING DAYS 85
Price Range \$ 3,000,000 to \$ 6,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 3.0 %

Plans and specifications may be seen beginning March 20, 2012 at the Lincoln Central Office and March 26, 2012 at the District Engineer's Office at NORFOLK
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	99 SHEETS	\$	24.75
CROSS SECTIONS (SHEETS X1 THRU X90)	90 SHEETS	\$	22.50
STANDARD PLANS	18 SHEETS	\$	4.25

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T3	TYPICAL CROSS SECTIONS
2-S1 - 2-S2	SUMMARY OF QUANTITIES
2-W1 - 2-W11	WETLANDS
2-H1 - 2-H8	HORIZONTAL ALIGNMENT & CONTROL POINTS
2-N1 - 2-N4	GENERAL INFORMATION
2-L1 - 2-L18	EROSION CONTROL
3 - 13	PLAN SHEETS
14	PAVEMENT MARKING PLAN
15	TEMPORARY PAVEMENT MARKING PLAN
16 - 19	EARTHWORK DATA SHEETS
20 - 22	DRAINAGE STRUCTURE CROSS SECTIONS
23	SPECIAL PLAN 1C CONCRETE DITCH LINER STA. 136+00.00
24 - 25	SPECIAL PLAN 2C HEADWALL WITH WINGS & PAVED APRON STA. 213+20.00
26 - 27	SPECIAL PLAN 3C EXTEND PARAPET & WING WALLS STA. 235+29.00 LT.
28 - 29	SPECIAL PLAN 4C TEMPORARY SILT CHECKS
R1 - R25	RIGHT-OF-WAY SHEETS
X1 - X90	CROSS SECTIONS

STANDARD PLANS

108-R4	SUPERELEVATION PLAN FOR CONCRETE AND BITUMINOUS SURFACING
301-R10	(3 SHEETS) PAVEMENT DETAILS
307-R1	MAILBOX TURNOUT
309	MAILBOX SUPPORT POST
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
804	PRECAST CONCRETE R.O.W. MARKER
901-R9	HIGHWAY DELINEATORS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION	11,373	CY
WATER	59	MGAL
RIGHT-OF-WAY MARKERS	45	EACH
RIPRAP FILTER FABRIC	60	SY
REMOVE ASPHALT SURFACE	215	SY
REMOVE DRIVEWAY	428	SY
24" DRIVE PIPE 2,3,4,5,6,7 OR 8	58	LF
36" DRIVE PIPE 2,3,4,5,6,7 OR 8	288	LF
48" DRIVE PIPE 2,3,4 OR 5	120	LF
CONCRETE DITCH LINING	80	SY
REMOVE FLARED- END SECTION	2	EACH
CULVERT CLEANOUT	1	EACH
AT STA. 626+64		
CULVERT CLEANOUT	1	EACH
AT STA. 626+84		
PREPARATION OF STRUCTURE	1	EACH
AT STA. 235+29		
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	5	CY
47B-3000 CONC FOR HDWL	4	CY
47B-3000 CONC FOR BOX CULV	1	CY
RE-STEEL FOR HEADWALL	220	LB
RE-STEEL FOR BOX CULVERT	280	LB
24" METAL FLARED-END SECTION	1	EACH
ROCK RIPRAP, TYPE B	43	TON
COVER CROP SEEDING	25	ACRE
EROSION CONTROL, CLASS 1E	4,626	SY
FABRIC SILT FENCE-LOW POROSITY	2,540	LF
24" CULV PIPE 3,4,5	8	LF
30" CULV PIPE 3,4,5	12	LF

GROUP 9 BITUMINOUS

OVERLAY BROKEN LINES	1,857	STA
OVERLAY SOLID LINES	3,714	STA
MOBILIZATION	LUMP	LUMP
DELINEATOR, TYPE III	31	EACH
GRAVEL SURFACE COURSE	235	CY
SPEC SURF CRSE FOR MAILBOX TURNOUTS	1,441	SY
MAILBOX POST	22	EACH
CONC 47B-3500 DRIVEWAY	145	SY
4" WHT WET RFLC PRF PVM T4 GVD	400	LF
4" YEL WET RFLC PRF PVM T4 GVD	7,900	LF
12" YEL WET RFLC PRF PVM T4 GVD	700	LF
HYDRATED LIME FOR ASPHALT MIXTURES	707	TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	5	TON
GRANULAR SUBDRAIN	100	EACH
ASPH CONC FOR ST MAINT PTCHING, TYPE SPR	500	TON
ASPH CONC, TYPE SPR	70,160	TON
PLACE ASPH CONC FOR DRIVE & INTER	5,043	SY
ASPH CONCRETE FOR PATCHING, TYPE SPR	500	TON
PERF GRAD BIND (64-34)FOR ST MAINT PATCH	19	TON
PERF GRADED BINDER (64-34)	2,685	TON
PREP OF INTER & DRIVE	630	SY
TACK COAT	38,280	GAL
WATER	310	MGAL
EARTH SHOULDER CONSTRUCTION	1,238	STA
TRENCHED WIDENING	1,191	STA
COLD MILLING, CLASS 3	167,792	SY
COLD MILLING, CLASS 5	541	SY
RAP INCENTIVE PAYMENT	120,122	EACH
ASPH PVM T SMOOTHNESS TESTING I/D	LUMP	LUMP

SEEDING, TYPE A	4 ACRE
SEEDING, TYPE B	21 ACRE
MULCH	56 TON

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	20,625 BDAY
BARRICADE, TYPE III	584 BDAY
TEMPORARY SIGN DAY	1,190 EACH
SIGN DAY	17,987 EACH
FLAGGING	170 DAY
FURNISHING AND OPERATING PILOT VEHICLE	80 DAY
FIELD OFFICE	1 EACH
TRAINING	500 HOUR
MOBILIZATION	LUMP LUMP
RENTAL OF LOADER, FULLY OPERATED	105 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	60 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	105 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	105 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	45 HOUR
TEMPORARY SILT CHECK	1,000 LF
TEMPORARY SILT FENCE	2,000 LF
TEMPORARY MULCH	4 TON