

STATE OF NEBRASKA  
DEPARTMENT OF ROADS  
ADDENDUM NO. 3  
AND  
ELECTRONIC BIDDING SYSTEM  
AMENDMENT NO. 3  
PROJECT NO. BR-8-6(106)  
CONTROL NO. 11678  
CALL NO. 100  
N-8, BARNESTON WEST  
LETTING DATE: MAY 17, 2012

The Schedule of Items is amended as follows:

1. In Group 10, the bid item "Temporary Silt Check" has been added with a quantity of 2,500.000 LF.

The EBS generated bid items sheets must show this correction or the bid will be considered void.

\* \* \* \* \*

On page 41 of the Special Provisions, paragraph 2 in the provision titled **SPECIAL PROSECUTION AND PROGRESS (General Requirements)** is amended to include the following:

The Contractor may be required to construct a work platform on one (or both) bank above the ordinary high water elevation to provide a level working surface. This work platform(s) shall be protected with silt fence or erosion checks. The shop plans for the work platform(s) shall be designed by a registered professional engineer.

It will be the Contractor's responsibility to submit a plan of the work platform(s) to the NDOR Environmental Unit for review with regard to impacts to delineated areas within the project. Construction of these platforms shall not begin without written approval from NDOR.

\* \* \* \* \*

The Special Provisions are amended to include the following:

**EROSION CHECKS**

Subsection 808.01 in the Standard Specifications is void and superseded by the following:

This work shall consist of seeding, trenching, furnishing and placing soil retention blankets, and furnishing and placing hay bales to construct erosion checks at the locations shown in the plans. There are two separate and distinct types of erosion checks – "Erosion Checks" which are permanent and placed as shown in the plans or as directed by the Engineer after final grading is complete; and "Temporary Silt Checks" which are temporary and placed as

shown in the plans or as directed by the Engineer when rough grading is begun or as necessary.

Subsection 808.02 in the Standard Specifications is amended as follows:

1. Paragraph 4. is void.
2. Paragraph 5a. is void and superseded by the following:
  - 5a. The "Temporary Silt Checks" shall be restricted to products which do not use a plastic or jute fiber net material in their construction, and are on the NDR Approved Products List.
3. Paragraph 5b. is void and superseded by the following:
  - 5b. The wire staples for "Temporary Silt Checks" shall be a minimum of 13 gauge steel wire with a 1 inch (25 mm) or larger throat and 6 inch (150 mm) legs.

Subsection 808.03 in the Standard Specifications is amended as follows:

1. Paragraph 3. is void.
2. Paragraph 4. is void.
3. Paragraph 6b. is void.
4. Paragraph 7. is void and superseded by the following:
  7. The hay bales shall then be placed in the trench over the soil retention blanket with bale ties up and backfilled to the level of the finished ditch elevation.
5. Paragraph 12, 12a, 12b, 12c, and 12d are void and superseded by the following:

Paragraph 12. Temporary Silt Checks

  - a. The "Temporary Silt Checks" shall be installed at the locations shown in the plans, and as directed by the Engineer. The upstream edge shall be slightly buried and pinned with wire staples on approximately 24 inch (600 mm) spacings. The pins may be left slightly exposed for easier removal. The triangular portion shall be pinned on 3 foot (1 m) centers.
  - b. The "Temporary Silt Check" shall be in place immediately after the rough grading is completed in that area.
  - c. The "Temporary Silt Check" shall be left in place until the finish grading begins. Reinstall the "Temporary Silt Checks" as soon as finish grading is complete unless the permanent erosion control is initiated immediately after

finish grading. "Temporary Silt Checks" should be in place at all times after finish grading until the permanent "Erosion Checks" are in place.

d. At the completion of the project, the "Temporary Silt Checks" shall remain the property of the Contractor.

Paragraph 2. in Subsection 808.04 in the Standard Specifications is void and superseded by the following:

2. "Temporary Silt Checks" shall be measured by the linear foot (meter) for the initial installation. The removing or relocating of the "Temporary Silt Checks" will not be measured for payment, but will be considered subsidiary to the initial installation.

Subsection 808.05 in the Standard Specifications is amended as follows:

Paragraphs 1, 2, and 3 are void and superseded by the following:

- | 1. Pay Item                    | Pay Unit                     |
|--------------------------------|------------------------------|
| Erosion Check                  | Bale                         |
| Erosion Checks, Type _____     | Bale                         |
| Erosion Checks, Type Wattle    | Linear Foot (LF) [Meter (m)] |
| Erosion Check "Type Synthetic" | Linear Foot (LF) [Meter (m)] |
| Temporary Silt Check           | Linear Foot (LF) [Meter (m)] |
| Erosion Checks, Type _____     | Linear Foot (LF) [Meter (m)] |
2. If cleanout of an "Erosion Check" or "Temporary Silt Check" is required, it will be paid as equipment rental as prescribed in Subsections 809.04 and 809.05.
  3. Payment for "Temporary Silt Checks" includes any costs incurred to reinstall the "Temporary Silt Checks" once the area is finished graded.

\* \* \* \* \*

Upon execution of the contract, the plans will be revised to reflect this change.

DEPARTMENT OF ROADS

***Original Signed By Kendall Stege***

For Claude Oie  
Construction Engineer

Issued: May 14, 2012

CO:100AD305

NOTICE: Only the contractors issued bidding proposals receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the contractor.