

NOTICE TO CONTRACTORS

CALL ORDER 300
 STATE PROJECT NO. RD-30-5(1045)
 LOCATION: US-30, COLUMBUS EAST
 COUNTIES: COLFAX PLATTE

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on May 17, 2012. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 5.2 MILES
 START DATE 07/23/2012 WORKING DAYS 55
 Price Range \$ 1,000,000 to \$ 3,000,000

Plans and specifications may be seen beginning April 24, 2012 at the Lincoln Central Office and April 30, 2012 at the District Engineer's Office at NORFOLK
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	28	SHEETS	\$	7.00
STANDARD PLANS	6	SHEETS	\$	1.50

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T4	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-A1 - 2-A7	PHOTO MAPS
2-H1 - 2-H2	HORIZONTAL ALIGNMENT & ORIENTATION
2-N1	GENERAL INFORMATION
2-N2 - 2-N3	GENERAL INFORMATION--MILLED RUMBLE STRIPS
3 - 9	PLAN SHEETS
10	TYPICAL TRAFFIC CONTROL PLAN--TYPICAL LANE CLOSURE (FREEWAY-INTERSTATE)
11	TEMPORARY PAVEMENT MARKING PLAN
12	TYPICAL PAVEMENT MARKING PLAN--5" PAVEMENT MARKING

STANDARD PLANS

920-R5	(2 SHEETS)	TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS)	TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS)	TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	14,040	B	DAY
BARRICADE, TYPE III	470	B	DAY
TEMPORARY SIGN DAY	420	E	EACH
SIGN DAY	3,660	E	EACH
OVERLAY BROKEN LINES	822	S	TA
OVERLAY SOLID LINES	1,644	S	TA
FLASHING ARROW PANEL	54	D	DAY
MOBILIZATION	LUMP	L	LUMP
CONC PVMT REPAIR TYPE B FULL DEPTH	415	C	Y
CONC PVMT REPAIR TYPE C FULL DEPTH	151	C	Y
5" WHT WET RFLC THERMOPLSTC PVMT MRK,GVD	36,500	L	F
5" YEL WET RFLC THERMOPLSTC PVMT MRK,GVD	27,500	L	F
HYDRATED LIME FOR ASPHALT MIXTURES	192	T	ON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	5	T	ON
FOUNDATION COURSE REPLACEMENT	9	C	Y

ASPH CONC 4 ST MAIN PTCHING TY SPH	500 TON
ASPH CONC, TYPE SPS	2,750 TON
ASPH CONC, TYPE SPH	18,130 TON
PLACE ASPH CONC FOR DRIVE & INTER	2,117 SY
ASPH CONC FOR PATCHING, TYPE SPH	1,000 TON
PERF GRAD BIND (70-34)FOR ST MAINT PATCH	17 TON
PERF GRADED BINDER (70-34)	918 TON
PERF GRADED BINDER (52-34)	96 TON
TACK COAT	20,600 GAL
RENTAL OF LOADER, FULLY OPERATED	50 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	50 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	50 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	50 HOUR
WATER	69 MGAL
EARTH SHOULDER CONSTRUCTION	272 STA
COLD MILLING, CLASS 3	272 STA
COLD MILLING, CLASS 5	2,117 SY
COLD MILLING, CLASS 3	272 STA
TYPE A	
COLD MILLING, CLASS 3	1,977 SY
TYPE B	
RUMBLE STRIPS, ASPHALT	548 STA
RAP INCENTIVE PAYMENT	37,196 EACH
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP LUMP
SEEDING, TYPE B	1 ACRE
HYDROMULCH	2 TON