

NOTICE TO CONTRACTORS

CALL ORDER 600
 FEDERAL PROJECT NO. NH-2-3(118)
 LOCATION: N-2, IN BROKEN BOW
 COUNTIES: CUSTER

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on May 17, 2012. At that time the bids will be opened and read for CULV ELEC BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS
 START DATE 08/13/2012 WORKING DAYS 45
 Price Range \$ 250,000 to \$ 1,000,000
 THIS PROJECT CONTAINS A DBE GOAL OF 4.0 %

Plans and specifications may be seen beginning April 24, 2012 at the Lincoln Central Office and April 30, 2012 at the District Engineer's Office at NORTH PLATTE
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	66	SHEETS	\$	16.50
STANDARD PLANS	24	SHEETS	\$	6.00
SHEET NO.				

1	TITLE PAGE
2-T1 - 2-T8	TYPICAL CROSS SECTIONS
2-S1 - 2-S3	SUMMARY OF QUANTITIES
2-A1 - 2-A7	PHOTO MAPS
2-H1 - 2-H2	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
2-L1 - 2-L7	GEOMETRICS
2-L8 - 2-L14	REMOVALS
3 - 9	PLAN SHEETS--CONSTRUCTION
10 - 13	PLAN SHEETS--LIGHTING
14 - 18	TRAFFIC SIGNAL PLANS
19 - 20	PAVEMENT MARKING PLAN
21	PAVEMENT MARKING PLAN--PARKING DETAIL
22	TEMPORARY PAVEMENT MARKING PLAN
23	DRAINAGE STRUCTURE CROSS SECTIONS
R1 - R8	RIGHT-OF-WAY SHEETS

STANDARD PLANS

301-R10	(3 SHEETS) PAVEMENT DETAILS
303	(2 SHEETS) CURB RAMP
329-R9	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
425-R4	COLLARS AND ELBOWS FOR CONCRETE PIPES
443-R8	(2 SHEETS) CURB INLETS AND JUNCTION BOX
914-R6	PULL BOX DETAIL
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING
924	(3 SHEETS) TYPICAL URBAN TRAFFIC CONTROL PLAN

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
REMOVE INLET		1 EACH
CAST IRON COVER & FRAME		125 LB
STRUCTURAL STEEL FOR FACE ARMOR		215 LB

REMOVE SEWER PIPE	43 LF
47B-3000 CONC FOR INLET & JUNCTION BOXES	4 CY
47B-3000 CONC FOR CONCRETE CO	1 CY
RE-STEEL FOR INLET & JCT BOX	292 LB
RE-STEEL FOR COLLARS	106 LB
CURB INLET SEDIMENT FILTER	1 EACH
30" STORM SEWER PIPE 1,7,8	38 LF

GROUP 8B ELECTRICAL

	LUMP	LUMP
MOBILIZATION		
PULL BOX, TYPE PB-1		1 EACH
PULL BOX, TYPE PB-2		1 EACH
PULL BOX, TYPE PB-5		2 EACH
PULL BOX, TYPE PB-6		1 EACH
TRAFFIC SIGNAL, TYPE TS-1		10 EACH
PEDESTRIAN SIGNAL, TYPE PS-1		16 EACH
VEHICLE DETECTOR, TYPE A PREFORMED		9 EACH
VEHICLE DETECTOR, TYPE B PREFORMED		1 EACH
C.M.A. SIG & LGHT POLE, CMP-25-8		1 EACH
C.M.A. SIG & LGHT POLE, CMP-30-8		2 EACH
C.M.A. SIG & LGHT POLE, CMP-35-8		1 EACH
C.M.A. SIG & LGHT POLE, CMP-40-8		1 EACH
LED TRAF SIG MOD, TYPE 12" RED		2 EACH
LED TRAF SIG MOD, TYPE 12" YELLOW		2 EACH
LED TRAF SIG MOD, TYPE 12" GREEN		2 EACH
1" CONDUIT IN TRENCH		50 LF
GALVANIZED RIGID STEEL		
2" CONDUIT IN TRENCH		3 LF
2" CONDUIT UNDER ROADWAY		41 LF
2" CONDUIT UNDER SIDEWALK		10 LF
1" CONDUIT, JACKED		45 LF
GALVANIZED RIGID STEEL		
2" CONDUIT, JACKED		258 LF
2/C #14 AWG TRAF SIG CABLE		218 LF
3/C #14 AWG TRAF SIG CABLE		520 LF
12/C #14 AWG TRAF SIG CABLE	1,	141 LF
2/C #14 AWG DETECTOR LEAD-IN CABLE		332 LF
GROUNDING CONDUCTOR		680 LF
SERVICE CABLE		584 LF
STREET LIGHT CABLE, NO. 6 USE	1,	236 LF
STREET LIGHT CABLE, NO. 8 USE		190 LF
INSTALL		1 EACH
TRAFFIC SIGNAL CONTROLLER, TYPE TC-2		
REMOVE TRAFFIC SIGNAL		1 EACH
AT N-2 & 9TH AVE.		
REMOVE PEDESTRIAN SIGNAL HEAD		6 EACH
REMOVE PULL BOX		1 EACH
REMOVE COMB MAST ARM SIG AND LIGHT POLE		1 EACH
REMOVE GROUNDING CONDUCTOR		241 LF
REMOVE SERVICE CABLE		296 LF
REMOVE TRAFFIC SIGNAL CABLE	2,	792 LF
REMOVE STREET LIGHTING CABLE		354 LF
REMOVE		2 EACH
VIDEO CAMERA		
REMOVE		354 LF
COAXIAL CABLE		
RELOCATE STREET LIGHTING UNIT		1 EACH

GROUP 9 BITUMINOUS

OVERLAY BROKEN LINES		129 STA
OVERLAY SOLID LINES		129 STA
PERMANENT PAVEMENT MARKING PAINT		1,200 LF
MOBILIZATION	LUMP	LUMP
RE-ESTABLISH PROPERTY CORNER		12 EACH
REMOVE PAVEMENT		407 SY
SAWING PAVEMENT		461 LF

REMOVE WALK	406 SY
TIE BARS	168 EACH
CONCRETE CURB REPAIR	654 LF
CONC 47B-3000 SIDEWALKS	473 SY
DETECTABLE WARNING PANEL	552 SF
CONC PVMT REPAIR TYPE A FULL DEPTH	7 CY
CONC PVMT REPAIR TYPE B FULL DEPTH	74 CY
CONC PVMT REPAIR TYPE C FULL DEPTH	626 CY
CONC PVMT REPAIR TYPE A PARTIAL DEPTH	1 CY
9" CONC PVMT 47B-HE-3500	439 SY
SEALING CRACKS	658 LF
SEALING JOINTS	28,017 LF
CONC PVMT, PR-3500	5 CY
JOINT REPAIR	
ARROW, PREF PVMT MRKING T-4 GROOVED	24 EACH
24" WHITE PREF PVMT MKING T-4 GROOVED	300 LF
5" WHT WET RFLC PRF PVMT MKNG T4 GVD	900 LF
5" YEL WET RFLC PRF PVMT MKNG T4 GVD	8,100 LF
HYDRATED LIME FOR ASPHALT MIXTURES	22 TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	3 TON
FOUNDATION COURSE REPLACEMENT	21 CY
ASPH CONC FOR ST MAINT PTCHING, TYPE SPR	300 TON
ASPH CONC, TYPE SPR	2,190 TON
ASPH CONCRETE FOR PATCHING, TYPE SPR	100 TON
PERF GRAD BIND (64-34)FOR ST MAINT PATCH	10 TON
PERF GRADED BINDER (64-34)	80 TON
TACK COAT	3,015 GAL
RENTAL OF LOADER, FULLY OPERATED	10 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	10 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	10 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	10 HOUR
WATER	3 MGAL
EARTH SHOULDER CONSTRUCTION	1 STA
SUBGRADE PREPARATION	439 SY
COLD MILLING, CLASS 3	20,103 SY
RAP INCENTIVE PAYMENT	3,893 EACH
ASPH PVMT SMOOTHNESS TESTING	LUMP LUMP
SODDING	82 SY

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	3,750 BDAY
BARRICADE, TYPE III	90 BDAY
SIGN DAY	2,586 EACH
CONTRACTOR FURNISHED SIGN DAY	132 EACH
FLAGGING	30 DAY
MOBILIZATION	LUMP LUMP