

NOTICE TO CONTRACTORS

CALL ORDER 100  
 FEDERAL PROJECT NO. BRO-7055(102)  
 LOCATION: ON A COUNTY ROAD, SOUTHEAST OF MALCOLM  
 COUNTIES: LANCASTER

The Nebraska Department of Roads will receive sealed bids for the COUNTY OF LANCASTER in Room 104 of the Central Office Building at 1500 Hwy 2 at Lincoln, until 1:30 P.M. on July 26, 2012. At that time the bids will be opened and read for GRAD CULV BR GDRL

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BRIDGES

START DATE 10/01/2012 WORKING DAYS 85  
 Price Range \$ 250,000 to \$ 1,000,000  
 THIS PROJECT CONTAINS A DBE GOAL OF 5.0 %

Plans and specifications may be seen beginning July 03, 2012 at the Lincoln Central Office and July 09, 2012 at the District Engineer's Office at LINCOLN. Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	34	SHEETS	\$	8.50
CROSS SECTIONS (SHEETS X1 THRU X12)	12	SHEETS	\$	3.00
STANDARD PLANS	14	SHEETS	\$	3.50

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS OF IMPROVEMENT
2-S	SUMMARY OF QUANTITIES
2-L1	INTERSECTION & GUARDRAIL DETAILS
2-L2	EROSION CONTROL PLAN
2-L3	STREAM CROSSING DETAIL & DETOUR LOCATION PLAN
3 - 4	PLAN & PROFILE SHEETS
5 - 6	DRAINAGE STRUCTURE CROSS SECTIONS
7 - 16	SPECIAL PLAN 1 PRESTRESSED CONCRETE IT-500 GIRDER BRIDGE STA. 51+37.50
17 - 25	SPECIAL PLAN 1C GUARDRAIL PROTECTION
26	SPECIAL PLAN 2C EROSION CHECKS (ALL TYPES) & FABRIC SILT CHECKS
27 - 28	SPECIAL PLAN 3C TEMPORARY SILT CHECKS
29	SPECIAL PLAN 4C CONCRETE HEADWALLS FOR PIPE & PIPE ARCH CULVERTS
R1	RIGHT-OF-WAY PLANS
X1 - X8	ROADWAY CROSS SECTIONS
X9 - X12	CHANNEL CROSS SECTIONS

STANDARD PLANS

411	(4 SHEETS) BEDDING AND BACKFILL REQUIREMENTS FOR CONCRETE PIPE
425-R4	COLLARS AND ELBOWS FOR CONCRETE PIPES
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL		13 EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)		9,109 CY
WATER		26 MGAL
CRUSHED ROCK EMBEDMENT		13 STA
CRUSHED ROCK SURFACE COURSE		640 TON
SEEDING, TYPE A		3 ACRE
COVER CROP SEEDING		4 ACRE
EROSION CONTROL, CLASS 1D		6,122 SY
EROSION CHECKS, TYPE WATTLE		312 LF
FABRIC SILT FENCE-LOW POROSITY		944 LF
FABRIC SILT FENCE-HIGH POROSITY		124 LF
MULCH		8 TON

GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
REMOVE HEADWALLS FROM CULV		1 EACH
REMOVE CULVERT PIPE		152 LF
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL		493 CY
47B-3000 CONC FOR HDWL		3 CY
RE-STEEL FOR HEADWALL		255 LB
30" RND EQ CULV PIPE 2,4,5		58 LF
24" CULV PIPE 3,4,5,6		90 LF
30" CULV PIPE 3,4,5,6		82 LF
36" CULV PIPE 2,4,5,7,8		216 LF

GROUP 6 BRIDGE AT STA. 51+37.50

MOBILIZATION	LUMP	LUMP
RIPRAP FILTER FABRIC		1,535 SY
ABUTMENT NO.1 EXCAVATION	LUMP	LUMP
ABUTMENT NO.2 EXCAVATION	LUMP	LUMP
BENT NO.1 EXCAVATION	LUMP	LUMP
BENT NO.2 EXCAVATION	LUMP	LUMP
47B-3000 CONC FOR BRIDGE		178 CY
47BD-4000 CONC FOR BRIDGE		133 CY
PRECAST/PRESTRESSED CONC SUPERSTR 51+37.50	LUMP	LUMP
RE-STEEL FOR BRIDGE		50,140 LB
REMOVE STRUCTURE AT STA. 51+50.50		1 EACH
ACCESS CROSSING	LUMP	LUMP
STRUC STEEL FOR SUBSTRUCTURE		9,580 LB
ROCK RIPRAP, TYPE B		1,295 TON
SALVAGING AND PLACING TOPSOIL ON RIPRAP		1,535 SY
HP 12"X53# STEEL PILING		2,180 LF
STEEL SHEET PILING		4,438 SF

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
W-BEAM GUARDRAIL		75 LF
BRIDGE APPROACH SECTIONS		4 EACH
MELT		4 EACH

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III		3,408 BDAY
SIGN DAY		5,082 EACH
CONTRACTOR FURNISHED SIGN DAY		618 EACH
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED		15 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED		15 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED		15 HOUR

RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	15 HOUR
TEMPORARY SILT CHECK	500 LF
TEMPORARY SILT FENCE	500 LF
TEMPORARY EARTH CHECK	500 LF
TEMPORARY MULCH	2 TON