

NOTICE TO CONTRACTORS

CALL ORDER 300
FEDERAL PROJECT NO. STPE-3875(2)
LOCATION: ON A COUNTY ROAD, NORTHEAST OF CRAIG
COUNTIES: BURT

The Nebraska Department of Roads will receive sealed bids for the
COUNTY OF BURT in Room 104 of the Central Office Building at
1500 Hwy 2 at Lincoln, until 1:30 P.M. on July 26, 2012.
At that time the bids will be opened and read for
CONC PAVE

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR
WHO IS QUALIFIED FOR: CONCRETE PAVEMENT

Length: 4.9 KILOMETERS
START DATE 09/24/2012 WORKING DAYS 30
Price Range \$ 500,000 to \$ 2,000,000

Plans and specifications may be seen beginning July 03, 2012 at the Lincoln
Central Office and July 09, 2012 at the District Engineer's Office at NORFOLK

Additional letting information may be found at the Nebraska Department of Roads
Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal
requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	14 SHEETS	\$	3.50
STANDARD PLANS	15 SHEETS	\$	3.75

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS OF IMPROVEMENT
2-S	SUMMARY OF QUANTITIES
2-H	CONTROL POINT TIES & DETOUR LOCATION MAP
3 - 10	PLAN & PROFILE SHEETS
11	TYPICAL PAVEMENT MARKING PLAN--125 mm PAVEMENT MARKING
12	SPECIAL PLAN 1C INTERSECTION DETAIL STA. 58+24.090

STANDARD PLANS

M301-R3	(3 SHEETS) PAVEMENT DETAILS
M308	LOCAL ROADS MAILBOX TURNOUT
M309	MAILBOX SUPPORT POST
M329-R6	(4 SHEETS) 203 TO 406 mm CONCRETE PAVEMENT
M502	SILT FENCE DETAILS
M920	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
M921-R1	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
M923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and
should not be used for bidding purposes. The Department
reserves the right to change these quantities without notice.

GROUP 3 CONCRETE PAVEMENT

BARRICADE, TYPE III	1,063 BDAY
SIGN DAY	1,311 EACH
CONTRACTOR FURNISHED SIGN DAY	345 EACH
PERMANENT PAVEMENT MARKING PAINT	12,135 m
MOBILIZATION	LUMP LUMP
ROADWAY GRADING	48 StaM
REMOVE ASPHALT SURFACE	243 m2
SPEC SURF CRSE FOR MAILBOX TURNOUTS	158 m2
MAILBOX POST	6 EACH
CONC 47B-25 DRIVEWAY	687 m2
205 mm DOWELED CONC PAVE, CLASS 47B-25	33,203 m2

PREP OF INTER & DRIVE	1,958 m2
RENTAL OF LOADER, FULLY OPERATED	5 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	5 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	5 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	5 HOUR
WATER	898 kL
EARTH SHOULDER CONSTRUCTION	96 StaM
SUBGRADE PREPARATION	48 StaM
SEEDING, TYPE B	1 ha
FABRIC SILT FENCE-LOW POROSITY	136 m
MULCH	6 Mg