

NOTICE TO CONTRACTORS

CALL ORDER 110
FEDERAL PROJECT NO. BR-3265(5)
LOCATION: ON A COUNTY ROAD, IN WYMORE
COUNTIES: GAGE

The Nebraska Department of Roads will receive sealed bids for the
COUNTY OF GAGE in Room 104 of the Central Office Building at
1500 Hwy 2 at Lincoln, until 1:30 P.M. on August 30, 2012.
At that time the bids will be opened and read for
GR CONC PAVE CULV BR GDRL

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR
WHO IS QUALIFIED FOR: BRIDGES

START DATE 05/13/2013 WORKING DAYS 115
Price Range \$ 500,000 to \$ 2,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 5.0 %

Plans and specifications may be seen beginning August 07, 2012 at the Lincoln
Central Office and August 13, 2012 at the District Engineer's Office at LINCOLN
Additional letting information may be found at the Nebraska Department of Roads
Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal
requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	34	SHEETS	\$	8.50
CROSS SECTIONS (SHEETS X1 THRU X7)	7	SHEETS	\$	1.75
STANDARD PLANS	21	SHEETS	\$	5.25

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS OF IMPROVEMENT
2-S	SUMMARY OF QUANTITIES
2-W	WETLANDS
2-N1 - 2-N2	GENERAL INFORMATION & DETOUR LOCATION MAP
2-L1 - 2-L2	JOINTS & GRADES
2-L3 - 2-L4	EROSION CONTROL
3	PLAN & PROFILE SHEET
4	TYPICAL PAVEMENT MARKING PLAN--5" PAVEMENT MARKING
5	DRAINAGE STRUCTURE CROSS SECTIONS
6 - 14	SPECIAL PLAN 1 CONCRETE SLAB BRIDGE STA. 17+20.00
15 - 22	SPECIAL PLAN 1C GUARDRAIL PROTECTION
23	SPECIAL PLAN 2C EROSION CHECKS (ALL TYPES) & FABRIC SILT CHECKS
24 - 25	SPECIAL PLAN 3C TEMPORARY SILT CHECKS
R1	RIGHT-OF-WAY DATA
X1 - X7	CROSS SECTIONS

STANDARD PLANS

301-R10	(3 SHEETS) PAVEMENT DETAILS
308-R1	LOCAL ROADS MAILBOX TURNOUT
309	MAILBOX SUPPORT POST
329-R9	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
425-R4	COLLARS AND ELBOWS FOR CONCRETE PIPES
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and
should not be used for bidding purposes. The Department
reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL		1 EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		77 MGAL
EARTHWORK MEASURED IN EMBANKMENT		11,022 CY
REMOVE ASPHALT SURFACE		4,132 SY
24" DRIVE PIPE 2,3,4,5,6,7 OR 8		130 LF
SEEDING, TYPE A		4 ACRE
SEEDING, TYPE B		1 ACRE
COVER CROP SEEDING		5 ACRE
EROSION CONTROL, CLASS 1D		4,290 SY
EROSION CONTROL, CLASS 2A		95 SY
EROSION CHECKS, TYPE 1D		18 BALE
FABRIC SILT FENCE-LOW POROSITY		2,213 LF
MULCH		11 TON

GROUP 3 CONCRETE PAVEMENT

PERMANENT PAVEMENT MARKING PAINT		5,259 LF
MOBILIZATION	LUMP	LUMP
CRUSHED ROCK SURFACE COURSE		14 TON
SPEC SURF CRSE FOR MAILBOX TURNOUTS		69 SY
MAILBOX POST		2 EACH
CONC 47B-3500 DRIVEWAY		264 SY
8" DOWELED CONC PAVE, CLASS 47B-3500		4,070 SY
FOUNDATION COURSE		4,070 SY
4"		
GRANULAR SUBDRAIN		24 EACH
PREP OF INTER & DRIVE		264 SY
WATER		21 MGAL
EARTH SHOULDER CONSTRUCTION		30 STA
SUBGRADE PREPARATION		4,070 SY

GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL		130 CY
36" FLARED-END SECTION		1 EACH
42" CONCRETE FLARED-END SECTION		2 EACH
42" CULV PIPE 2		60 LF
36" CULV PIPE 3,4,5,6		74 LF

GROUP 6 BRIDGE AT STA 17+20.00

MOBILIZATION	LUMP	LUMP
RIPRAP FILTER FABRIC		1,932 SY
CONC FOR PVMT APPROACHES CLASS 47BD-4000		132 CY
RE-STEEL FOR PAVEMENT APPROACHES		21,265 LB
ABUTMENT NO.1 EXCAVATION	LUMP	LUMP
ABUTMENT NO.2 EXCAVATION	LUMP	LUMP
BENT NO.1 EXCAVATION	LUMP	LUMP
BENT NO.2 EXCAVATION	LUMP	LUMP
47B-3000 CONC FOR BRIDGE		217 CY
47BD-4000 CONC FOR BRIDGE		313 CY
RE-STEEL FOR BRIDGE		69,625 LB
REMOVE STRUCTURE		1 EACH
AT STA 17+23.00		
ACCESS CROSSING	LUMP	LUMP
STRUC STEEL FOR SUBSTRUCTURE		1,785 LB
ROCK RIPRAP, TYPE B		1,635 TON
SALVAGING AND PLACING TOPSOIL ON RIPRAP		1,932 SY
HP 12"X53# STEEL PILING		1,190 LF
ROCK SOCKET		104 LF
30"		

DRILLED SHAFT	136 LF
36"	
STEEL SHEET PILING	2,743 SF

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
BRIDGE APPROACH SECTIONS		4 EACH
MELT		4 EACH

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III	2,828 BDAY
SIGN DAY	3,636 EACH
CONTRACTOR FURNISHED SIGN DAY	808 EACH
TRAINING	500 HOUR
MOBILIZATION	LUMP
RENTAL OF LOADER, FULLY OPERATED	30 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	30 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	30 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	30 HOUR
TEMPORARY SILT CHECK	300 LF
TEMPORARY SILT FENCE	500 LF
TEMPORARY EARTH CHECK	300 LF
TEMPORARY MULCH	2 TON