

NOTICE TO CONTRACTORS

CALL ORDER 205
FEDERAL PROJECT NO. BH-HSIP-275-6(141)
LOCATION: US-275, SCRIBNER NORTH
COUNTIES: DODGE

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on August 30, 2012. At that time the bids will be opened and read for BR GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BRIDGES

START DATE 07/08/2013 WORKING DAYS 80
Price Range \$ 250,000 to \$ 1,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 3.0 %

Plans and specifications may be seen beginning August 07, 2012 at the Lincoln Central Office and August 13, 2012 at the District Engineer's Office at OMAHA

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	44	SHEETS	\$	11.00
CROSS SECTIONS (SHEETS X1 THRU X9)	9	SHEETS	\$	2.25
STANDARD PLANS	13	SHEETS	\$	3.25

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-W1 - 2-W4	WETLANDS
2-H1 - 2-H3	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
3 - 6	PLAN SHEETS
7	TYPICAL TRAFFIC SIGNAL CONTROL PLAN FOR ONE LANE, TWO WAY OPERATION WITH BARRIERS
8	TEMPORARY TRAFFIC SIGNAL
9	TEMPORARY PAVEMENT MARKING PLAN
10 - 11	EARTHWORK DATA SHEETS
12 - 14	SPECIAL PLAN 1 BRIDGE REPAIR STA. 190+67.17
15 - 16	SPECIAL PLAN 2 REMODEL BRIDGE RAIL STA. 213+16.99
17 - 25	SPECIAL PLAN 3 BRIDGE REPAIR STA. 1022+51.31
26 - 29	SPECIAL PLAN 4 BRIDGE REPAIR STA. 1217+93.05
30 - 33	SPECIAL PLAN 1C GUARDRAIL PLAN
34 - 35	SPECIAL PLAN 2C CONCRETE PROTECTION BARRIER
X1 - X9	CROSS SECTIONS

STANDARD PLANS

501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
740	MIDWEST GUARDRAIL SYSTEM BRIDGE APPROACH SECTION
743	(4 SHEETS) GUARDRAIL DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 6 BRIDGE AT STA 190+67.17

MOBILIZATION	LUMP	LUMP
ASPHALT PLUG JOINT SYSTEM		84 LF
47BD-4000 CONC FOR BRIDGE		5 CY
PREP BRIDGE		1 EACH
190+67.17		
EPOXY COATED RE-STEEL		1,281 LB

GROUP 6A BRIDGE AT STA 213+16.99

MOBILIZATION	LUMP	LUMP
47BD-4000 CONC FOR BRIDGE		9 CY
PREP BRIDGE		1 EACH
AT STA 213+16.99		
EPOXY COATED RE-STEEL		2,190 LB
CONCRETE REPAIR		5 SF

GROUP 6B BRIDGE AT STA 1022+51.31

MOBILIZATION	LUMP	LUMP
PREFORMED EXPANSION JOINT, TYPE A		7 LF
47BD-4000 CONC FOR BRIDGE		122 CY
RE-STEEL FOR BRIDGE		21,379 LB
PREP BRIDGE		1 EACH
1022+51.31		
STRUC STEEL FOR SUPERSTRUCTURE		820 LB
FLOOR DRAINS		14 EACH
PIN REPLACEMENT		1 EACH
CONCRETE REPAIR		20 SF

GROUP 6C BRIDGE AT STA 1217+93.05

MOBILIZATION	LUMP	LUMP
47B-3000 CONC FOR BRIDGE		42 CY
47BD-4000 CONC FOR BRIDGE		6 CY
PREP BRIDGE		1 EACH
1217+93.05		
EPOXY COATED RE-STEEL		4,508 LB
CONCRETE REPAIR		5 SF

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
W-BEAM GUARDRAIL		750 LF
REMOVE GUARDRAIL		1,600 LF
BRIDGE APPROACH SECTIONS		16 EACH
GUARDRAIL END TREATMENT, TYPE II		16 EACH

GROUP 9 BITUMINOUS

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		17 MGAL
EARTHWORK MEASURED IN EMBANKMENT		792 CY
REMOVE ASPHALT SURFACE		750 SY
SURFACING 8"		712 SY
EARTH SHOULDER CONSTRUCTION		8 STA
SUBGRADE PREPARATION		712 SY
SURFACE UNDER GUARDRAIL		1,216 SY
EROSION CONTROL, CLASS 1D		3,376 SY
FABRIC SILT FENCE-LOW POROSITY		840 LF

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	1,520	BDAY
BARRICADE, TYPE III	760	BDAY
SIGN DAY	9,500	EACH
TEMP PAVEMENT MARKING REMOVAL	13,800	LF
PAVEMENT MARKING REMOVAL	4,150	LF
TEMP PVMT MARKING, TYPE PAINT	14,300	LF
TEMP PVMT MARKING SURF PREP	14,300	LF
FLAGGING	16	DAY
CONCRETE PROTECTION BARRIER	1,025	LF
RELOCATE CONC PROTECTION BARRIER	3,075	LF
TEMPORARY RUMBLE STRIP	16	EACH
TEMPORARY TRAFFIC SIGNAL	4	EACH
TRAFFIC CONTROL MANAGEMENT	146	DAY
FIELD OFFICE	1	EACH
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED	10	HOURL
RENTAL OF DUMP TRUCK, FULLY OPERATED	10	HOURL
RENTAL OF SKID LOADER, FULLY OPERATED	10	HOURL
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	10	HOURL
TEMPORARY SILT FENCE	300	LF