

NOTICE TO CONTRACTORS

CALL ORDER 410
STATE PROJECT NO. MISC-81-1(1045)
LOCATION: US-81, HEBRON NORTH
COUNTIES: THAYER

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on August 30, 2012. At that time the bids will be opened and read for GRADING

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: GRADING

START DATE 10/22/2012 WORKING DAYS 20
Price Range \$ 0 to \$ 500,000

Plans and specifications may be seen beginning August 07, 2012 at the Lincoln Central Office and August 13, 2012 at the District Engineer's Office at GRAND ISLAND. Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	23 SHEETS	\$	5.75
CROSS SECTIONS (SHEETS X1 THRU X3)	3 SHEETS	\$	0.75
STANDARD PLANS	10 SHEETS	\$	2.25

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-W	WETLANDS
2-H1 - 2-H2	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
2-L1 - 2-L2	CONSTRUCTION & REMOVALS
2-L3 - 2-L4	EROSION CONTROL
3 - 4	PLAN & PROFILE SHEETS
5	EARTHWORK DATA SHEET
6	DRAINAGE STRUCTURE CROSS SECTIONS
7 - 8	SPECIAL PLAN 1C CONCRETE DITCH LINER STA. 3500+83.00 RT
9	SPECIAL PLAN 2C CONCRETE HEADWALL (FOR 12" TO 30" CORRUGATED METAL PIPES WITH NO SKEW)
10	SPECIAL PLAN 3C EROSION CHECKS (ALL TYPES) & FABRIC SILT CHECKS
11 - 12	SPECIAL PLAN 4C TEMPORARY SILT CHECKS
R1 - R2	RIGHT-OF-WAY SHEETS
X1 - X3	CROSS SECTIONS

STANDARD PLANS

410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
501-R5	(3 SHEETS) EROSION CONTROL
804	PRECAST CONCRETE R.O.W. MARKER
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

TEMPORARY SIGN DAY	46 EACH
MOBILIZATION	LUMP LUMP
GENERAL CLEARING AND GRUBBING	LUMP LUMP
EXCAVATION	11,446 CY
WATER	11 MGAL

RIGHT-OF-WAY MARKERS	9 EACH
SALVAGING AND PLACING TOPSOIL	11,000 SY
CONCRETE DITCH LINING	26 LF
REMOVE FLARED- END SECTION	3 EACH
REMOVE HEADWALLS FROM CULV	2 EACH
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	124 CY
47B-3000 CONC FOR HDWL	1 CY
RE-STEEL FOR HEADWALL	128 LB
24" METAL FLARED-END SECTION	1 EACH
30" METAL FLARED-END SECTION	1 EACH
CULVERT SANDFILL	74 CY
SEEDING, TYPE A	2 ACRE
COVER CROP SEEDING	2 ACRE
EROSION CONTROL, CLASS 1D	2,552 SY
EROSION CONTROL, CLASS 2A	824 SY
EROSION CHECKS, TYPE 2A	50 BALE
EROSION CHECKS, TYPE WATTLE	160 LF
TEMPORARY SILT CHECK	500 LF
TEMPORARY EARTH CHECK	500 LF
TEMPORARY MULCH	1 TON
MULCH	5 TON
24" CULV PIPE 3,4,5,6	22 LF
30" CULV PIPE 3,4,5,6	56 LF