

NOTICE TO CONTRACTORS

CALL ORDER 110
FEDERAL PROJECT NO. STP-34-7(125)
LOCATION: US-34, N-63-N-50
COUNTIES: CASS

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on October 04, 2012. At that time the bids will be opened and read for BR GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 10.7 MILES
START DATE 04/15/2013 WORKING DAYS 115
Price Range \$ 3,000,000 to \$ 6,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 4.0 %

Plans and specifications may be seen beginning September 11, 2012 at the Lincoln Central Office and September 17, 2012 at the District Engineer's Office at LINCOLN
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$ 5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	49	SHEETS	\$ 12.25
CROSS SECTIONS (SHEETS X1 THRU X2)	2	SHEETS	\$ 0.50
STANDARD PLANS	19	SHEETS	\$ 4.75

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T5	TYPICAL CROSS SECTIONS
2-S1 - 2-S3	SUMMARY OF QUANTITIES
2-W1 - 2-W11	WETLANDS
2-H1 - 2-H5	HORIZONTAL ALIGNMENT & ORIENTATION
2-N1	GENERAL INFORMATION
2-N2 - 2-N3	GENERAL INFORMATION--MILLED RUMBLE STRIPS
2-N4	GENERAL INFORMATION
3 - 12	PLAN SHEETS
13	PAVEMENT MARKING PLAN
14	TEMPORARY PAVEMENT MARKING PLAN
15	TYPICAL PAVEMENT MARKING PLAN--5" PAVEMENT MARKING
16	TYPICAL PAVEMENT MARKING PLAN--4" PAVEMENT MARKING
17	EARTHWORK DATA SHEET
18 - 19	SPECIAL PLAN 1 BRIDGE REPAIR STA. 563+93.50
20	SPECIAL PLAN 1C GUARDRAIL PLAN
21 - 22	SPECIAL PLAN 2C TEMPORARY SILT CHECKS
X1 - X2	CROSS SECTIONS

STANDARD PLANS

301-R10	(3 SHEETS) PAVEMENT DETAILS
309	MAILBOX SUPPORT POST
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
740	MIDWEST GUARDRAIL SYSTEM BRIDGE APPROACH SECTION
743	(4 SHEETS) GUARDRAIL DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 6 BRIDGE AT STA. 563+93.50

MOBILIZATION	LUMP	LUMP
MULTI-LAYER POLYMER CONCRETE OVERLAY	308	SY
PREP BRIDGE	1	EACH
AT STA. 563+93.50		
PENETRATING CONCRETE SEALER	922	SF
CONCRETE REPAIR	25	SF
REPAIR FLOOR DRAIN	6	EACH
BRIDGE APPROACH REPAIR	1	CY

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
W-BEAM GUARDRAIL	175	LF
REMOVE GUARDRAIL	462	LF
BRIDGE APPROACH SECTIONS	4	EACH
GUARDRAIL END TREATMENT, TYPE II	4	EACH

GROUP 9 BITUMINOUS

OVERLAY BROKEN LINES	1,654	STA
OVERLAY SOLID LINES	3,424	STA
MOBILIZATION	LUMP	LUMP
EARTHWORK MEASURED IN EMBANKMENT	143	CY
REMOVE PAVEMENT	145	SY
SAWING PAVEMENT	1,751	LF
REMOVE ASPHALT SURFACE	213	SY
REMOVE CONCRETE MEDIAN SURFACING	793	SY
MAILBOX POST	21	EACH
TIE BARS	637	EACH
8" CONCRETE BASE COURSE	938	SY
CONC PVMT REPAIR TYPE A FULL DEPTH	544	CY
CONC PVMT REPAIR TYPE B FULL DEPTH	1,031	CY
CONC PVMT REPAIR TYPE C FULL DEPTH	530	CY
4" WHT WET RFLC PRF PVMT MKNG T4 GVD	500	LF
12" WHT WET RFLC PRF PVMT MKNG T4 GVD	65	LF
4" YEL WET RFLC PRF PVMT MKNG T4 GVD	6,750	LF
12" YEL WET RFLC PRF PVMT MKNG T4 GVD	450	LF
HYDRATED LIME FOR ASPHALT MIXTURES	272	TON
FOUNDATION COURSE REPLACEMENT	38	CY
ASPH CONC, TYPE SPS	11,202	TON
ASPH CONC, TYPE SPH (0.5)	33,596	TON
PLACE ASPH CONC FOR DRIVE & INTER	6,214	SY
ASPH CONC FOR PATCHING, TYPE SPH (0.5)	500	TON
PERF GRADED BINDER (70-34)	1,193	TON
PERF GRADED BINDER (52-34)	392	TON
TACK COAT	46,678	GAL
WATER	3	MGAL
SUBGRADE PREPARATION	938	SY
COLD MILLING, CLASS 3	574	STA
COLD MILLING, CLASS 5	6,214	SY
COLD MILLING, CLASS 3	1,118	STA
TYPE A		
RUMBLE STRIPS, ASPHALT	1,069	STA
SURFACE UNDER GUARDRAIL	193	SY
RAP INCENTIVE PAYMENT	77,007	EACH
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
EROSION CONTROL, CLASS 1D	916	SY

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	30,000	B DAY
BARRICADE, TYPE III	808	B DAY
TEMPORARY SIGN DAY	1,610	EACH
SIGN DAY	25,331	EACH
FLAGGING	220	DAY
FURNISHING AND OPERATING PILOT VEHICLE	100	DAY

FIELD OFFICE		1 EACH
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED		50 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED		50 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED		50 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED		50 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.		5 HOUR
TEMPORARY SILT CHECK		200 LF
TEMPORARY SILT FENCE		200 LF