

NOTICE TO CONTRACTORS

CALL ORDER 600
 FEDERAL PROJECT NO. STP-183-3(116)
 LOCATION: US-183, COMSTOCK SOUTH
 COUNTIES: CUSTER

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on October 04, 2012. At that time the bids will be opened and read for GRAD SEED BR GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 9.5 MILES
 START DATE 05/20/2013 WORKING DAYS 95
 Price Range \$ 3,000,000 to \$ 6,000,000
 THIS PROJECT CONTAINS A DBE GOAL OF 3.0 %

Plans and specifications may be seen beginning September 11, 2012 at the Lincoln Central Office and September 17, 2012 at the District Engineer's Office at NORTH PLATTE

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	72	SHEETS	\$	18.00
CROSS SECTIONS (SHEETS X1 THRU X27)	27	SHEETS	\$	6.75
STANDARD PLANS	18	SHEETS	\$	4.50

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T4	TYPICAL CROSS SECTIONS
2-S1 - 2-S2	SUMMARY OF QUANTITIES
2-W1 - 2-W9	WETLANDS
2-H1 - 2-H3	HORIZONTAL ALIGNMENT & ORIENTATION
2-N1	GENERAL INFORMATION
2-N2 - 2-N3	GENERAL INFORMATION--MILLED RUMBLE STRIPS
2-N4	GENERAL INFORMATION
3 - 11	PLAN SHEETS
12 - 14	TRAFFIC SIGNAL CONTROL PLANS FOR NARROW BRIDGE, ONE LANE, TWO WAY OPERATION WITH BARRIERS (10')
15	TEMPORARY TRAFFIC SIGNAL
16	TEMPORARY PAVEMENT MARKING PLAN
17 - 18	EARTHWORK DATA SHEETS
19	DRAINAGE STRUCTURE CROSS SECTIONS
20 - 23	SPECIAL PLAN 1 BRIDGE REPAIR STA. 516+50.00
24 - 25	SPECIAL PLAN 2 BRIDGE REPAIR STA. 530+30.00
26 - 29	SPECIAL PLAN 3 BRIDGE REPAIR STA. 905+16.00
30 - 39	SPECIAL PLAN 1C GUARDRAIL PLANS
40 - 44	SPECIAL PLAN 2C CABLE GUARDRAIL
45	SPECIAL PLAN 3C CONCRETE FLUME, TYPE I
46 - 47	SPECIAL PLAN 4C CONCRETE FLUME, TYPE IV
48 - 49	SPECIAL PLAN 5C TEMPORARY SILT CHECKS
50 - 51	SPECIAL PLAN 6C CONCRETE PROTECTION BARRIER
X1 - X27	CROSS SECTIONS

STANDARD PLANS

307-R1	MAILBOX TURNOUT
309	MAILBOX SUPPORT POST
428-R3	CONCRETE PLUGS AND FIELD PIPE TAP DETAILS
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS

740	MIDWEST GUARDRAIL SYSTEM BRIDGE APPROACH SECTION
743	(4 SHEETS) GUARDRAIL DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		58 MGAL
EARTHWORK MEASURED IN EMBANKMENT	2,410	CY
REMOVE PAVEMENT	277	SY
REMOVE ASPHALT SURFACE	516	SY
REMOVE GUARDRAIL	2,699	LF
REMOVE & SALVAGE GUARDRAIL	387	LF
COVER CROP SEEDING	20	ACRE
EROSION CONTROL, CLASS 1D	5,261	SY
EROSION CONTROL, CLASS 1F	150	SY
FABRIC SILT FENCE-LOW POROSITY	1,378	LF

GROUP 5 SEEDING

MOBILIZATION	LUMP	LUMP
SEEDING, TYPE A		1 ACRE
SEEDING, TYPE B		19 ACRE
MULCH		45 TON

GROUP 6 BRIDGE AT STA. 516+50.00

MOBILIZATION	LUMP	LUMP
BR DECK REPAIR, PARTIAL DEPTH		46 SY
BR DECK REPAIR, FULL DEPTH		5 SY
47BD-4000 CONC FOR BRIDGE		19 CY
PREP BRIDGE		1 EACH
516+50.00		
EPOXY COATED RE-STEEL	3,499	LB
REPAIR FLOOR DRAIN		6 EACH

GROUP 6A BRIDGE AT STA. 530+30.00

MOBILIZATION	LUMP	LUMP
BR DECK REPAIR, PARTIAL DEPTH		69 SY
BR DECK REPAIR, FULL DEPTH		5 SY

GROUP 6B BRIDGE AT STA. 905+16.00

MOBILIZATION	LUMP	LUMP
BR DECK REPAIR, PARTIAL DEPTH		33 SY
BR DECK REPAIR, FULL DEPTH		5 SY
47BD-4000 CONC FOR BRIDGE		14 CY
PREP BRIDGE		1 EACH
905+16.00		
EPOXY COATED RE-STEEL	2,576	LB
CONCRETE REPAIR		7 SF
REPAIR FLOOR DRAIN		3 EACH

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
W-BEAM GUARDRAIL		931 LF
CABLE GUARDRAIL	1,137	LF
RESET GUARDRAIL	387	LF
BRIDGE APPROACH SECTIONS		8 EACH
TERMINAL ANCHORAGE SECTIONS		4 EACH
GUARDRAIL END TREATMENT, TYPE I		5 EACH

GUARDRAIL END TREATMENT, TYPE II 5 EACH

GROUP 9 BITUMINOUS

OVERLAY BROKEN LINES	1,500	STA
OVERLAY SOLID LINES	3,000	STA
MOBILIZATION	LUMP	LUMP
REMOVE GRATE INLET	1	EACH
GRAVEL SURFACE COURSE	140	CY
SPEC SURF CRSE FOR MAILBOX TURNOUTS	1,139	SY
MAILBOX POST	16	EACH
FLUME SPILLWAY	22	LF
CONCRETE FLUME, TYPE I	2	EACH
CONCRETE FLUME, TYPE IV	2	EACH
47B-3000 CONC FOR PIPE PLUG	1	CY
MEMBRANE WATERPROOFING	840	SY
HYDRATED LIME	477	TON
HYDRATED LIME FOR ASPHALT MIXTURES	1,720	TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	18	TON
HYDRATED LIME SLURRY STABILIZATION	497	STA
ASPH CONC FOR ST MAIN PTCHG TY SPR(FINE)	300	TON
ASPH CONC, TYPE SPR (FINE)	28,180	TON
PLACE ASPH CONC FOR DRIVE & INTER	5,059	SY
ASPH CONC FOR PATCHING, TYPE SPR (FINE)	500	TON
PERF GRAD BIND (64-34)FOR ST MAINT PATCH	10	TON
PERF GRADED BINDER (64-34)	1,003	TON
CONSTRUCTING ASPH CONC CURB	2,835	LF
EMUL ASPH FOR HYDRATE LIME STABILIZATION	121,910	GAL
TACK COAT	32,241	GAL
FOG SEAL	15,480	GAL
WATER	256	MGAL
EARTH SHOULDER CONSTRUCTION	1,001	STA
TRENCHED WIDENING	995	STA
SUBGRADE PREPARATION	1,850	SY
COLD MILLING, CLASS 4	794	SY
COLD MILLING, CLASS 5	3,467	SY
MILLING FOR ASPH CONC INLAY	8	EACH
RUMBLE STRIPS, ASPHALT	995	STA
SURFACE UNDER GUARDRAIL	1,732	SY
RAP INCENTIVE PAYMENT	48,756	EACH
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
15" CULV PIPE 3,4,5,6	68	LF

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	9,576	BDAY
BARRICADE, TYPE III	1,100	BDAY
TEMPORARY SIGN DAY	560	EACH
SIGN DAY	13,070	EACH
TEMP PAVEMENT MARKING REMOVAL	11,300	LF
PAVEMENT MARKING REMOVAL	4,200	LF
TEMP PVMT MARKING, TYPE PAINT	12,400	LF
TEMP PVMT MARKING SURF PREP	12,400	LF
FLAGGING	80	DAY
FURNISHING AND OPERATING PILOT VEHICLE	40	DAY
CONCRETE PROTECTION BARRIER	800	LF
RELOCATE CONC PROTECTION BARRIER	1,550	LF
TEMPORARY RUMBLE STRIP	12	EACH
TEMPORARY TRAFFIC SIGNAL	3	EACH
FIELD OFFICE	1	EACH
TRAINING	1,000	HOUR
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED	70	HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	50	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	70	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	70	HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	20	HOUR
TEMPORARY SILT CHECK	100	LF
TEMPORARY SILT FENCE	500	LF
TEMPORARY MULCH	4	TON