

NOTICE TO CONTRACTORS

CALL ORDER 750
 FEDERAL PROJECT NO. URB-6154(1)
 LOCATION: 'H' STREET, NORRIS AVE.-AIRPORT RD., McCOOK
 COUNTIES: RED WILLOW

The Nebraska Department of Roads will receive sealed bids for the CITY OF MCCOOK in Room 104 of the Central Office Building at 1500 Hwy 2 at Lincoln, until 1:30 P.M. on October 25, 2012. At that time the bids will be opened and read for CONC PAVE WATER MAIN

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CONCRETE PAVEMENT

Length: 1.3 MILES
 START DATE 05/06/2013 WORKING DAYS 105
 Price Range \$ 500,000 to \$ 2,000,000
 THIS PROJECT CONTAINS A DBE GOAL OF 2.0 %

Plans and specifications may be seen beginning October 02, 2012 at the Lincoln Central Office and October 09, 2012 at the District Engineer's Office at MCCOOK. Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	31	SHEETS	\$	7.75
CROSS SECTIONS (SHEETS X1 THRU X2)	2	SHEETS	\$	0.50
STANDARD PLANS	9	SHEETS	\$	2.25

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-A	PHOTO MAP
2-P	PHASING PLAN
2-L1 - 2-L2	EROSION CONTROL
3 - 15	PLAN & PROFILE SHEETS
16	PLAN & PROFILE SHEET--TEMPORARY ACCESS ROAD
17 - 21	PLAN SHEETS--REMOVALS
22	PLAN SHEET--STORM SEWER
23	PLAN SHEET--WATER MAIN & SERVICES
24	PLAN SHEET--SIGNAGE
25 - 26	SPECIAL PLAN 1C TEMPORARY SILT CHECKS
X1 - X2	CROSS SECTIONS

STANDARD PLANS

425-R4	COLLARS AND ELBOWS FOR CONCRETE PIPES
502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
924	(3 SHEETS) TYPICAL URBAN TRAFFIC CONTROL PLAN

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 3 CONCRETE PAVEMENT

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EARTHWORK MEASURED IN EMBANKMENT		334 CY
REMOVE PAVEMENT		8,630 SY
SAWING PAVEMENT		918 LF

REMOVE ASPHALT SURFACE	57 SY
REMOVE DRIVEWAY	1,086 SY
REMOVE WALK	1,183 SY
REMOVE COMBINATION CURB AND GUTTER	3,715 LF
GRAVEL SURFACE COURSE	140 CY
TIE BARS	3,760 EACH
COMB CONC 47B-3500 CURB & GUTTER 6"	3,803 LF
COMB CONC 47B-3500 CURB & GUTTER 8"	520 LF
CONC 47B-3000 SIDEWALKS	1,814 SY
DETECTABLE WARNING PANEL	640 SF
CONC 47B-3500 DRIVEWAY	271 SY
8" CONC PVMT, 47B-4000	24,178 SY
ADJUST GRATE INLET TO GRADE	15 EACH
ADJUST CURB INLET TO GRADE	1 EACH
ADJUST MANHOLE TO GRADE	12 EACH
CURB INLET SEDIMENT FILTER	2 EACH
BROKEN CONCRETE RIPRAP	3 TON
FOUNDATION COURSE 3"	24,178 SY
PREP OF INTER & DRIVE WATER	271 SY 77 MGAL
EARTH SHOULDER CONSTRUCTION	12 STA
SUBGRADE PREPARATION	24,178 SY
COLD MILLING, CLASS 4	21,561 SY
SEEDING, TYPE B	1 ACRE
SODDING	344 SY
FABRIC SILT FENCE-LOW POROSITY	2,274 LF
HYDROMULCH	1 TON
ADJUST VALVE BOX TO GRADE	8 EACH

GROUP 4A WATER MAIN

	LUMP	LUMP
MOBILIZATION		
REMOVE JUNCTION BOX		1 EACH
CAST IRON RING & COVER		450 LB
REMOVE SEWER PIPE		110 LF
47B-3000 CONC FOR INLET & JUNCTION BOXES		2 CY
47B-3500 CONCRETE FOR CONCRETE COLLARS		1 CY
RE-STEEL FOR INLET & JCT BOX		183 LB
RE-STEEL FOR COLLARS		58 LB
36" REINF CONCRETE SEWER PIPE		105 LF
18" CORR POLY PIPE		20 LF
CURB STOP		6 EACH
2" LINE STOP		1 EACH
4" LINE STOP		1 EACH
1" CORPORATION STOP		6 EACH
WATER SERVICE		113 LF
4" WATER MAIN PIPE PVC		7 LF
6" WATER MAIN PIPE PVC		45 LF
8" WATER MAIN PIPE PVC		569 LF
12" INSTA VALVE		1 EACH
6" GATE VALVE		3 EACH
8" GATE VALVE		2 EACH
FIRE HYDRANT		5 EACH
4" DRESSER COUPLING		1 EACH
6" DRESSER COUPLING		1 EACH
8" DRESSER COUPLING		1 EACH
16" X 8" TAPPING TEE		1 EACH
12" X 8" TAPPING TEE, M.J.		1 EACH
8" X 8" X 6" TEE		1 EACH
8" X 8" X 4" TEE		1 EACH
6" - 45 DEGREE BEND		1 EACH

GROUP 4B WATER MAIN

	LUMP	LUMP
MOBILIZATION		
6" WATER MAIN PIPE PVC	426	LF
6" GATE VALVE		3 EACH
FIRE HYDRANT		1 EACH
TAPPING TEE 6" X 6" X 6"		1 EACH
6" X 6" X 6" TEE		1 EACH
6" - 90 DEGREE BEND		1 EACH
8" - 45 DEGREE BEND		1 EACH
6" - 22 1/2 DEGREE BEND		2 EACH
8" X 6" REDUCER		1 EACH

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III	6,376	BDAY
SIGN DAY	1,688	EACH
CONTRACTOR FURNISHED SIGN DAY	1,538	EACH
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED	25	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	25	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	25	HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	25	HOUR
TEMPORARY SILT CHECK	200	LF
TEMPORARY SILT FENCE	300	LF