

NOTICE TO CONTRACTORS

CALL ORDER 315
FEDERAL PROJECT NO. NH-STP-81-3(143)
LOCATION: US-81, MADISON SOUTH (NB)
COUNTIES: MADISON PLATTE

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on December 13, 2012. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 4.1 MILES
START DATE 07/15/2013 WORKING DAYS 60
Price Range \$ 1,000,000 to \$ 3,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 2.0 %

Plans and specifications may be seen beginning November 20, 2012 at the Lincoln Central Office and November 26, 2012 at the District Engineer's Office at NORFOLK
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	17 SHEETS	\$	4.25
STANDARD PLANS	7 SHEETS	\$	1.75

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T6	TYPICAL CROSS SECTIONS
2-S1 - 2-S3	SUMMARY OF QUANTITIES
2-N	GENERAL INFORMATION
3	TYPICAL TRAFFIC CONTROL PLAN--TYPICAL LANE CLOSURE (FREEWAY-INTERSTATE)
4	TEMPORARY PAVEMENT MARKING PLAN
5	TYPICAL PAVEMENT MARKING PLAN--5" PAVEMENT MARKING
6	PAVEMENT MARKING DETAILS
7 - 8	SPECIAL PLAN 1C MILLED RUMBLE STRIPS

STANDARD PLANS

920-R5	(2 SHEETS)	TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS)	TRAFFIC CONTROL FOR ASPHALT SURFACING
924	(3 SHEETS)	TYPICAL URBAN TRAFFIC CONTROL PLAN

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	10,000	B DAY
BARRICADE, TYPE III	356	B DAY
TEMPORARY SIGN DAY	740	EACH
SIGN DAY	2,598	EACH
OVERLAY BROKEN LINES	1,093	STA
OVERLAY SOLID LINES	2,186	STA
FLASHING ARROW PANEL	50	DAY
FLAGGING	20	DAY
FURNISHING AND OPERATING PILOT VEHICLE	10	DAY
MOBILIZATION	LUMP	LUMP
REMOVE ASPH SURF FROM PAVEMENT	520	SY
CONC PVMT REPAIR TYPE A FULL DEPTH	1	CY
CONC PVMT REPAIR TYPE B FULL DEPTH	651	CY
CONC PVMT REPAIR TYPE C FULL DEPTH	119	CY

CONC PVMT, PR-3500	6 CY
JOINT REPAIR	
RR XING SYMBOL PREF PVMT MRKING T-4 GRVD	1 EACH
HYDRATED LIME FOR ASPHALT MIXTURES	97 TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	3 TON
FOUNDATION COURSE REPLACEMENT	17 CY
ASPH CONC FOR ST MAINT PTCHING, TYPE SPR	500 TON
ASPH CONC, TYPE SPS	6,820 TON
ASPH CONC, TYPE SPR	12,840 TON
ASPH CONC, TYPE SPR (FINE)	3,130 TON
PLACE ASPH CONC FOR DRIVE & INTER	2,681 SY
ASPH CONCRETE FOR PATCHING, TYPE SPR	200 TON
PERF GRAD BIND (64-34)FOR ST MAINT PATCH	17 TON
PERF GRADED BINDER (52-34)	238 TON
PERF GRADED BINDER (64-34)	565 TON
TACK COAT	27,070 GAL
RENTAL OF LOADER, FULLY OPERATED	30 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	30 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	30 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	30 HOUR
WATER	24 MGAL
EARTH SHOULDER CONSTRUCTION	92 STA
COLD MILLING, CLASS 3	364 STA
TYPE A	
COLD MILLING, CLASS 4	215 STA
COLD MILLING, CLASS 5	1,150 SY
COLD MILLING, CLASS 3	43 STA
COLD MILLING, CLASS 3	46 STA
TYPE B	
RUMBLE STRIPS, ASPHALT	364 STA
RAP INCENTIVE PAYMENT	39,100 EACH
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP LUMP
SEEDING, TYPE B	2 ACRE
MULCH	5 TON