

# NOTICE TO CONTRACTORS

CALL ORDER 400  
FEDERAL PROJECT NO. STP-30-4(155)  
LOCATION: US-30, BUFFALO/DAWSON COUNTY LINE EAST  
COUNTIES: BUFFALO DAWSON

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on December 13, 2012. At that time the bids will be opened and read for GRAD,CULV,BR,GDRL,ELEC,BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 12.5 MILES  
START DATE 04/01/2013 WORKING DAYS 120  
Price Range \$ 4,000,000 to \$ 7,000,000  
THIS PROJECT CONTAINS A DBE GOAL OF 5.0 %

Plans and specifications may be seen beginning November 20, 2012 at the Lincoln Central Office and November 26, 2012 at the District Engineer's Office at GRAND ISLAND  
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$ 5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	93	SHEETS	\$ 23.25
CROSS SECTIONS (SHEETS X1 THRU X15)	15	SHEETS	\$ 3.75
STANDARD PLANS	29	SHEETS	\$ 7.25
SHEET NO.			

1	TITLE PAGE
2-T1 - 2-T5	TYPICAL CROSS SECTIONS
2-S1 - 2-S3	SUMMARY OF QUANTITIES
2-W1 - 2-W23	WETLANDS
2-H1 - 2-H4	HORIZONTAL ALIGNMENT & ORIENTATION
2-N1	GENERAL INFORMATION
2-N2 - 2-N3	GENERAL INFORMATION-MILLED RUMBLE STRIPS
2-N4	GENERAL INFORMATION--SURFACED INTERSECTIONS & DRIVEWAYS
2-L1	GEOMETRICS
2-L2 - 2-L3	CONSTRUCTION & REMOVAL
3 - 14	PLAN SHEETS
15	TYPICAL TRAFFIC SIGNAL CONTROL PLAN FOR ONE LANE, TWO WAY OPERATION WITH BARRIERS
16	TEMPORARY TRAFFIC SIGNAL
17	TEMPORARY PAVEMENT MARKING PLAN
18	PAVEMENT MARKING PLAN
19	PAVEMENT MARKING DETAILS
20 - 23	ROADWAY LIGHTING PLANS
24	DRAINAGE STRUCTURE CROSS SECTIONS
25 - 28	SPECIAL PLAN 1 TWIN TEE BEAM BRIDGE REPAIR STA. 560+27.80
29 - 31	SPECIAL PLAN 2 TWIN TEE BEAM BRIDGE--REMODEL BRIDGE RAIL STA. 607+77.30
32 - 34	SPECIAL PLAN 3 STEEL GIRDER BRIDGE REPAIR STA. 679+91.53
35	SPECIAL PLAN 1C PAVEMENT APPROACH REPAIR
36 - 40	SPECIAL PLAN 2C GUARDRAIL PLAN
41 - 42	SPECIAL PLAN 3C CONCRETE PROTECTION BARRIER
R1 - R10	RIGHT-OF-WAY SHEETS
X1 - X15	CROSS SECTIONS

## STANDARD PLANS

301-R10	(3 SHEETS) PAVEMENT DETAILS
303	(2 SHEETS) CURB RAMP
410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
411	(4 SHEETS) BEDDING AND BACKFILL REQUIREMENTS FOR CONCRETE PIPE

425-R4	COLLARS AND ELBOWS FOR CONCRETE PIPES
428-R3	CONCRETE PLUGS AND FIELD PIPE TAP DETAILS
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
740	MIDWEST GUARDRAIL SYSTEM BRIDGE APPROACH SECTION
743	(4 SHEETS) GUARDRAIL DETAILS
804	PRECAST CONCRETE R.O.W. MARKER
901-R9	HIGHWAY DELINEATORS
914-R6	PULL BOX DETAIL
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

#### GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		20 MGAL
RIGHT-OF-WAY MARKERS		10 EACH
EARTHWORK MEASURED IN EMBANKMENT		891 CY
REMOVE ASPHALT SURFACE		3,664 SY
REMOVE DRIVEWAY		58 SY
REMOVE WALK		47 SY
24" DRIVE PIPE 2,3,4,5,6,7 OR 8		60 LF
REMOVE GUARDRAIL		1,055 LF
REMOVE SIGN, POST, AND FOOTING		3 EACH
COVER CROP SEEDING		15 ACRE
EROSION CONTROL, CLASS 1D		1,335 SY

#### GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
REMOVE FLARED- END SECTION		2 EACH
REMOVE HEADWALLS FROM CULV		2 EACH
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL		64 CY
47B-3000 CONC FOR PIPE PLUG		1 CY
24" FLARED-END SECTION		2 EACH
24" METAL FLARED-END SECTION		2 EACH
24" CULV PIPE 3,4,5		28 LF
24" CULV PIPE 2,4,5,7,8		74 LF

#### GROUP 6 BRIDGE AT STA 560+27.80

MOBILIZATION	LUMP	LUMP
CONC FOR PVMT APPROACHES CLASS 47BD-4000		7 CY
RE-STEEL FOR PAVEMENT APPROACHES		1,995 LB
PREP BRIDGE		1 EACH
560+27.80		
CONCRETE REPAIR		24 SF

#### GROUP 6A BRIDGE AT STA 607+77.30

MOBILIZATION	LUMP	LUMP
CONC FOR PVMT APPROACHES CLASS 47BD-4000		7 CY
RE-STEEL FOR PAVEMENT APPROACHES		1,995 LB
PREP BRIDGE		1 EACH
607+77.30		
CONCRETE REPAIR		8 SF

GROUP 6B BRIDGE AT STA 679+91.53

MOBILIZATION	LUMP	LUMP
CONC FOR PVTM APPROACHES CLASS 47BD-4000		7 CY
RE-STEEL FOR PAVEMENT APPROACHES	1,995	LB
PREP BRIDGE		1 EACH
679+91.53		
CONCRETE REPAIR	120	SF

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
W-BEAM GUARDRAIL	293	LF
BRIDGE APPROACH SECTIONS	16	EACH
END ANCHORAGE ASSEMBLY	1	EACH
GUARDRAIL END TREATMENT, TYPE II	15	EACH

GROUP 8B ELECTRICAL

MOBILIZATION	LUMP	LUMP
1 1/2" CONDUIT IN TRENCH	101	LF
1 1/2" CONDUIT UNDER ROADWAY	22	LF
1 1/2" CONDUIT, JACKED	110	LF
STREET LIGHT CABLE, NO. 6 BARE	233	LF
STREET LIGHT CABLE, NO. 6 USE	466	LF
RELOCATE STREET LIGHTING UNIT	2	EACH

GROUP 9 BITUMINOUS

OVERLAY BROKEN LINES	2,060	STA
OVERLAY SOLID LINES	4,120	STA
MOBILIZATION	LUMP	LUMP
DELINEATOR, TYPE III	26	EACH
CRUSHED ROCK SURFACE COURSE	35	CY
CONC 47B-3000 SIDEWALKS	47	SY
DETECTABLE WARNING PANEL	64	SF
CONC PVTM REPAIR TYPE A FULL DEPTH	4	CY
CONC PVTM REPAIR TYPE B FULL DEPTH	1,167	CY
CONC PVTM REPAIR TYPE C FULL DEPTH	266	CY
BRIDGE APPROACH REPAIR	6	CY
5" WHT WET RFLC PRF PVTM MKNG T4 GVD	420	LF
24" WHT WET RFLC PRF PVTM MKNG T4 GVD	90	LF
5" YEL WET RFLC PRF PVTM MKNG T4 GVD	4,000	LF
12" YEL WET RFLC PRF PVTM MKNG T4 GVD	250	LF
RR XING SYMBOL PREF PVTM MRKING T-4 GRVD	1	EACH
HYDRATED LIME FOR ASPHALT MIXTURES	429	TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	1	TON
FOUNDATION COURSE REPLACEMENT	26	CY
ASPH CONC FOR ST MAINT PTCHING, TYPE SPR	150	TON
ASPH CONC, TYPE SPS	13,430	TON
ASPH CONC, TYPE SPR	41,970	TON
PLACE ASPH CONC FOR DRIVE & INTER	1,477	SY
ASPH CONCRETE FOR PATCHING, TYPE SPR	1,000	TON
ASPH CONCRETE FOR PATCHING, TYPE SPS	500	TON
PERF GRAD BIND (64-34)FOR ST MAINT PATCH	5	TON
PERF GRADED BINDER (52-34)	487	TON
PERF GRADED BINDER (64-34)	1,503	TON
PREP OF INTER & DRIVE	724	SY
TACK COAT	56,020	GAL
WATER	24	MGAL
EARTH SHOULDER CONSTRUCTION	28	STA
SUBGRADE PREPARATION	4,569	SY
COLD MILLING, CLASS 3	659	STA
COLD MILLING, CLASS 3	83	STA
TYPE B		
COLD MILLING, CLASS 3	1,284	STA
TYPE A		
RUMBLE STRIPS, ASPHALT	1,332	STA

RUMBLE STRIPS, ASPHALT 8"	1,332	STA
SURFACE UNDER GUARDRAIL	579	SY
RAP INCENTIVE PAYMENT	96,730	EACH
ASPH PVTM SMOOTHNESS TESTING I/D	LUMP	LUMP
SEEDING, TYPE B	15	ACRE
MULCH	33	TON

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	29,400	BDAY
BARRICADE, TYPE III	4,128	BDAY
TEMPORARY SIGN DAY	1,120	EACH
SIGN DAY	25,072	EACH
TEMP PAVEMENT MARKING REMOVAL	10,300	LF
PAVEMENT MARKING REMOVAL	2,490	LF
TEMP PVTM MARKING, TYPE PAINT	10,300	LF
TEMP PVTM MARKING SURF PREP	4,180	LF
FLAGGING	204	DAY
FURNISHING AND OPERATING PILOT VEHICLE	102	DAY
CONCRETE PROTECTION BARRIER	1,062	LF
RELOCATE CONC PROTECTION BARRIER	1,062	LF
TEMPORARY RUMBLE STRIP	12	EACH
TEMPORARY TRAFFIC SIGNAL	3	EACH
TRAFFIC CONTROL MANAGEMENT	216	DAY
TRAINING	1,000	HOURL
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED	90	HOURL
RENTAL OF MOTOR GRADER, FULLY OPERATED	80	HOURL
RENTAL OF DUMP TRUCK, FULLY OPERATED	90	HOURL
RENTAL OF SKID LOADER, FULLY OPERATED	90	HOURL
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	10	HOURL
TEMPORARY SILT FENCE	1,000	LF