

# NOTICE TO CONTRACTORS

CALL ORDER 700  
FEDERAL PROJECT NO. STP-61-1(110)  
LOCATION: N-61, US-34 NORTH  
COUNTIES: DUNDY

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on December 13, 2012. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 7.6 MILES  
START DATE 07/29/2013 WORKING DAYS 50  
Price Range \$ 1,000,000 to \$ 3,000,000  
THIS PROJECT CONTAINS A DBE GOAL OF 2.0 %

Plans and specifications may be seen beginning November 20, 2012 at the Lincoln Central Office and November 26, 2012 at the District Engineer's Office at MCCOOK

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	23 SHEETS	\$	5.75
STANDARD PLANS	6 SHEETS	\$	1.50

## SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-A1 - 2-A7	PHOTO MAPS
2-H	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
3 - 9	PLAN SHEETS
10	TYPICAL TRAFFIC CONTROL PLAN--VEHICLE SIGNING FOR PAINT STRIPING
11	TEMPORARY PAVEMENT MARKING PLAN
12	PAVEMENT MARKING DETAILS
13	TYPICAL PAVEMENT MARKING PLAN--5" PAVEMENT MARKING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

## GROUP 9 BITUMINOUS

BARRICADE, TYPE II	8,750 BDAY
BARRICADE, TYPE III	485 BDAY
TEMPORARY SIGN DAY	700 EACH
SIGN DAY	7,760 EACH
OVERLAY BROKEN LINES	1,159 STA
OVERLAY SOLID LINES	2,318 STA
PERMANENT PAVEMENT MARKING PAINT	116,000 LF
FLAGGING	100 DAY
FURNISHING AND OPERATING PILOT VEHICLE	48 DAY
MOBILIZATION	LUMP LUMP
ROADWAY GRADING	5 STA
REMOVE ASPHALT SURFACE	130 SY
GRAVEL SURFACE COURSE	165 CY
SPEC SURF CRSE FOR MAILBOX TURNOUTS	508 SY
MAILBOX POST	6 EACH
STOP AHD SYM, PREF PVMT MRKING, T-4 GVD	1 EACH
HYDRATED LIME FOR ASPHALT MIXTURES	157 TON

HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	15 TON
ASPH CONC FOR ST MAINT PTCHING, TYPE SPR	2,500 TON
ASPH CONC, TYPE SPR	25,860 TON
PLACE ASPH CONC FOR DRIVE & INTER	3,705 SY
ASPH CONCRETE FOR PATCHING, TYPE SPR	300 TON
PERF GRAD BIND (64-34)FOR ST MAINT PATCH	88 TON
PERF GRADED BINDER (64-34)	916 TON
PREP OF INTER & DRIVE	288 SY
TACK COAT	21,172 GAL
RENTAL OF LOADER, FULLY OPERATED	40 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	40 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	40 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	40 HOUR
FLY ASH SLURRY INJECTION	273 TON
INJECTION HOLES	2,184 EACH
COLD MILLING, CLASS 3	386 STA
COLD MILLING, CLASS 5	3,417 SY
COLD MILLING, CLASS 3	386 STA
TYPE A	
RAP INCENTIVE PAYMENT	44,472 EACH
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP LUMP
SEEDING, TYPE B	2 ACRE
MULCH	5 TON